

This Page Is Inserted by IFW Operations  
and is not a part of the Official Record

## **BEST AVAILABLE IMAGES**

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images may include (but are not limited to):

- BLACK BORDERS
- TEXT CUT OFF AT TOP, BOTTOM OR SIDES
- FADED TEXT
- ILLEGIBLE TEXT
- SKEWED/SLANTED IMAGES
- COLORED PHOTOS
- BLACK OR VERY BLACK AND WHITE DARK PHOTOS
- GRAY SCALE DOCUMENTS

**IMAGES ARE BEST AVAILABLE COPY.**

**As rescanning documents *will not* correct images,  
please do not report the images to the  
Image Problem Mailbox.**

**THIS PAGE BLANK (USPTO)**



## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

<b>(51) International Patent Classification:</b> B65D 85/00, 81/00, C08L 23/10, C08K 3/34	<b>A1</b>	<b>(11) International Publication Number:</b> WO 99/48775 <b>(43) International Publication Date:</b> 30 September 1999 (30.09.99)
<b>(21) International Application Number:</b> PCT/US99/05465 <b>(22) International Filing Date:</b> 12 March 1999 (12.03.99) <b>(30) Priority Data:</b> 60/078,923 20 March 1998 (20.03.98) US <b>(71) Applicant:</b> FORT JAMES CORPORATION [US/US]; 1650 Lake Cook Road, P.O. Box 89, Deerfield, IL 60015 (US). <b>(72) Inventors:</b> COCHRAN, Ronald, L., II; 1002 Pembroke Drive, Neenah, WI 54956 (US). LITTLEJOHN, Mark, B.; 2430 W. Applegate Drive, Appleton, WI 54914 (US). McCARTHY, Donald, C.; 911 Foxmoor Lane, Appleton, WI 54911 (US). NECULESCU, Cristian, M.; 713 Kensington Road, Neenah, WI 54956 (US). PATTERSON, Robert; 8790 County Road B, Winneconne, WI 54986 (US). SWIONTEK, Anthony, J.; 6352 County Road A, Neenah, WI 54956 (US). <b>(74) Agent:</b> FERRELL, Michael, W.; Ferrell & Ferrell L.L.P., Suite 409, 90 Crystal Run Road, Middletown, NY 10941 (US).	<b>(81) Designated States:</b> AL, CA, JP, LT, LV, MK, RO, SI, European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE).  <b>Published</b> <i>With international search report.</i>	

**(54) Title:** DISPOSABLE, MICROWAVEABLE CONTAINERS AND PROCESS FOR THEIR MANUFACTURE**(57) Abstract**

Low-odor microwaveable polypropylene/mica food contact articles are disclosed. The articles are prepared by low temperature processing and typically include odor-suppressing basic organic or inorganic compounds. Preferably, the articles are substantially free from C8 and C9 organic ketones associated with undesirable odors. Further improvements to the articles include crack-resistant embodiments with synergistic amounts of polyethylene and titanium dioxide.

**FOR THE PURPOSES OF INFORMATION ONLY**

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece	ML	Mali	TR	Turkey
BG	Bulgaria	HU	Hungary	MN	Mongolia	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MR	Mauritania	UA	Ukraine
BR	Brazil	IL	Israel	MW	Malawi	UG	Uganda
BY	Belarus	IS	Iceland	MX	Mexico	US	United States of America
CA	Canada	IT	Italy	NE	Niger	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NL	Netherlands	VN	Viet Nam
CG	Congo	KE	Kenya	NO	Norway	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NZ	New Zealand	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	PL	Poland		
CM	Cameroon	KR	Republic of Korea	PT	Portugal		
CN	China	KZ	Kazakhstan	RO	Romania		
CU	Cuba	LC	Saint Lucia	RU	Russian Federation		
CZ	Czech Republic	LI	Liechtenstein	SD	Sudan		
DE	Germany	LK	Sri Lanka	SE	Sweden		
DK	Denmark	LR	Liberia	SG	Singapore		
EE	Estonia						

## DISPOSABLE, MICROWAVEABLE CONTAINERS AND PROCESS FOR THEIR MANUFACTURE

5 **Cross Reference to Related Application**

The present application is a non-provisional application based on United States Provisional Application Serial No. 60/078,923 filed March 20, 1998 of the same title, the priority of which is claimed.

10

**Background of the Invention**

Filled polypropylene articles have been observed to exhibit undesirable odors, particularly upon heating. In this respect, see United States Patent No. 5,023,286 to Abe et al., wherein phenolic antioxidants are suggested to control the odor problem. Other polypropylene compositions may be found in United States Patent Nos. 4,734,450 to Kawai et al.; United States Patent No. 5,045,369 to Kobayashi et al.; United States Patent No. 5,300,747 of Simon; United States Patent No. 5,439,628 of Huang and United States Patent No. 4,933,526 of Fisher et al.

20

This invention relates to disposable, polypropylene/mica microwaveable containers having suitable food contact compatible olfactory properties including cups, trays, soufflé dishes, lids, plates, bowls, and related articles of manufacture useful for preparation, storage, delivery, and serving of food, wherein convenience and low cost are of paramount importance. Nevertheless, suitable food contact compatible olfactory properties, appearance, and tactile characteristics of the plate, container, etc., are important for consumer preference. The suitability of these disposable articles of manufacture for microwave cooking, or heating of food, has an important place in today's marketplace. Both the commercial and retail market components need an aesthetically pleasing microwaveable, disposable, rigid and strong container, plate, or cup, and related articles of

25

30

manufacture which also have suitable food contact compatible olfactory properties.

5        These disposable microwaveable containers and plates exhibit a melting point of no less than about 250°F, the containers or plates being dimensionally stable and resistant to grease, sugar and water at temperatures up to at least 220°F and exhibiting sufficient toughness to be resistant to cutting by serrated polystyrene flatware and also exhibiting food contact compatible olfactory properties. The preferred containers and plates exhibit both suitable food contact  
10       compatible olfactory properties and at least one micronodular surface on the food contact side of the container or plate.

### Summary of the Invention

15        Microwaveable, disposable, rigid and strong containers and plates having suitable food contact compatible olfactory properties have been prepared. These disposable and microwaveable articles of manufacture exhibit (a) suitable food contact compatible olfactory properties; and (b) a melting point of not less than 250°F, suitably 250°F to 330°F. In preferred embodiments these articles of  
20       manufacture exhibit a micronodular surface on the side coming in contact with food. These microwaveable, food contact compatible containers and plates are dimensionally stable and resistant to grease, sugar and water at temperatures of at least 220°F and are of sufficient toughness to be resistant to cutting by serrated polystyrene flatware. The containers and plates of this invention answer a long  
25       felt need for products which can withstand the severe conditions of a microwave oven when common foods such as beans and pork, pancakes with syrup, pepperoni pizza, and broccoli with cheese are microwaved during food cooking and reconstituting processes.

30        It has been found in accordance with the present invention that polypropylene/mica food contact articles such as bowls or plates exhibit suitable

olfactory characteristics when prepared by a low temperature process and/or when prepared including a basic organic or inorganic compound. There is provided in a first aspect of the present invention, a microwaveable, disposable food service article having food contact compatible olfactory properties formed of a melt  
5 processed polyolefin/mica composition wherein the composition includes from about 40 to about 90% by weight of a polypropylene polymer and from about 10 to about 50% by weight mica where the melt processed composition exhibits low odor as characterized by a relative aroma intensity index of less than about 1.6. Less than about 1.5 is more preferred and, as a practical matter, the lower limit of  
10 the relative aroma intensity index for the inventive composition is believed to be about 0.1.

Typically, the melt processed composition from which the microwaveable article is formed also includes a basic organic or inorganic compound including  
15 the reaction product of an alkali metal or alkaline earth element with carbonates, phosphates, carboxylic acids as well as alkali metal and alkaline earth element oxides, hydroxides, or silicates and basic metal oxides including mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of the foregoing. More specifically,  
20 the basic organic or inorganic compound may be selected from the group consisting of: calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium citrate, potassium citrate, calcium stearate, potassium stearate, sodium phosphate, potassium phosphate,  
25 magnesium phosphate, mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the above. Furthermore, hydroxides of the metals and alkaline earth elements recited above may be utilized.

30 Where a basic inorganic odor suppressing compound is chosen, generally such compound is selected from the group consisting of calcium carbonate,

sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicone dioxide with one or more of the following oxides:

- 5 magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the basic inorganic compounds set forth above. The amount of a basic inorganic compound is generally from about 2 to 20 weight percent, but is usually from about 5 to about 15 weight percent of the article. Most preferably the basic inorganic compound selected is calcium carbonate; typically present from about 5  
10 to about 20 weight percent.

- Where an organic compound is chosen, it is typically selected from the group consisting of sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, and mixtures of these where the amount of such  
15 compound is from about 0.5 to about 2.5 weight percent of the article.

- Typically, microwaveable articles produced in accordance with the present invention exhibit a relative aroma intensity index of less than about 1.0 ; preferably less than about 0.7; with a practical lower limit being 0.1 or so.

- 20 As shown below in connection with microwaveability testing, and summarized in Table 20, competing commercial polystyrene type plates cannot withstand the high temperatures generated in the microwave oven during food contact and either significantly warp or deform when the aforementioned food  
25 products were heated on them. Under the usual microwaving conditions with high grease content foods, the prior art plates tend to deform and flow to the point where parts of the plate become adhered to the inside of the microwave oven. For disposable plates and containers, having suitable food contact olfactory properties, appearance and feel are important attributes. The micronodular surface of the  
30 plates and containers of this invention where mica and the basic inorganic compound or basic organic compound are used in combination with



polypropylene or polypropylene polyethylene copolymers or blends tend to give these products the pleasing appearance, feel of stoneware or a pottery-like look and suitable food contact olfactory properties. Another significant property of the containers and plates of this invention is their cut resistance. These rigid articles of manufacture are of sufficient toughness to be resistant to cutting by serrated polystyrene flatware. In normal usage they are also resistant to cutting by regular metal flatware.

Whereas any microwaveable article may be produced in accordance with the invention, most typically the article is a bowl or a plate suitable for serving food at a meal. The articles may be produced by injection molding; however, preferred articles are thermoformed and include a micronodular food contact surface. Micronodular food contact surfaces are produced by thermoforming a sheet into the article which has been extruded optionally with at least one matte roll and by vacuum thermoforming the sheet by applying vacuum opposite to the surface where the micronodular surface is desired. Most typically the micronodular surface will have a surface gloss of less than about 35 at 75° as measured by TAPPI method T-480-OM 92. Articles also will typically have a Parker Roughness Value of at least about 12 microns.

While any suitable polypropylene polymer may be used, the polypropylene polymers are preferably selected from the group consisting of isotactic polypropylene, and copolymers of propylene and ethylene wherein the ethylene moiety is less than about 10% of the units making up the polymer, and mixtures thereof. Generally, such polymers have a melt flow index from about 0.3 to about 4, but most preferably the polymer is isotactic polypropylene with a melt-flow index of about 1.5. In particularly preferred embodiments, the melt compounded composition from which the resultant extruded sheet is formed into articles further includes a polyethylene component and titanium dioxide. The polyethylene component may be any suitable polyethylene such as HDPE, LDPE, MDPE, LLDPE or mixtures thereof.

The various polyethylene polymers referred to herein are described at length in the Encyclopedia of Polymer Science & Engineering (2d Ed.), Vol. 6; pp: 383-522, Wiley 1986; the disclosure of which is incorporated herein by reference. HDPE refers to high density polyethylene which is substantially linear and has a density of generally greater than 0.94 up to about 0.97 g/cc. LDPE refers to low density polyethylene which is characterized by relatively long chain branching and a density of about 0.912 to about 0.925 g/cc. LLDPE or linear low density polyethylene is characterized by short chain branching and a density of from about 0.92 to about 0.94 g/cc. Finally, intermediate density polyethylene (MDPE) is characterized by relatively low branching and a density of from about 0.925 to about 0.94 g/cc. Unless otherwise indicated these terms have the above meaning throughout the description which follows.

The microwaveable articles according to the invention typically exhibit melting points from about 250 to about 330° F and include mica in amounts from about 20 to about 35 weight percent. Most preferably mica is present at about 30 weight percent.

It has been found that C8 and C9 organic ketones correlate well with or are associated with undesirable odors in polypropylene/mica compositions. Accordingly, it is preferred that articles in accordance with the invention are substantially free from volatile C8 and C9 organic ketones. In order to avoid undesirable odors, articles in accordance with the invention are preferably prepared from a melt compounded polyolefin mica composition which is prepared at a process melt temperature of less than about 425°F; with below about 400°F being even more preferred. Optionally, the melt processed polyolefin/mica composition is melt compounded in a nitrogen atmosphere.

In another aspect of the invention there is provided a microwaveable, disposable food contact article having food contact compatible olfactory

properties formed of a melt processed polyolefin/mica composition wherein said composition includes from about 40 to about 90 percent by weight of a polypropylene polymer and from about 10 to about 50 percent by weight mica and a basic organic or inorganic odor suppressing compound including the reaction product of an alkali-metal or an alkaline earth element with carbonates, phosphates, carboxylic acids as well as alkali metal and alkaline earth element oxides and silicates and basic metal oxides, including mixtures of silicone dioxides with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures thereof.

10

Preferably the inventive articles are prepared from a melt compounded polyolefin/mica composition prepared by way of a low temperature compounding process.

A preferred low temperature compounding process used for producing polypropylene/mica melt compounded compositions including a basic odor suppressing agent having olfactory properties suitable for food contact applications in accordance with the invention includes the sequential steps of: (a) preheating a polypropylene polymer while maintaining the polymer below a maximum temperature of about 350° F and more preferably below a maximum of about 260°F; but suitably above about 240° F; followed by; (b) admixing mica to said preheated polymer in an amount from about 10 to about 50 percent weight based on the combined weight of the resin and mica and maintaining the mixture below about 425°F; followed by, (c) extruding the mixture. Polymer may be melted exclusively through the application of shear, or the shear may be supplemented through heating by infrared radiation or ordinary heating coils or performed externally to the mixing chamber. Preferably, the basic odor suppressing agent is added simultaneously with the mica.

It is desirable to keep the duration of the step of admixing mica and a basic odor suppressant agent to the mixture relatively short so as not to generate compounds which cause odor and to preserve the particle size and aspect ratio of

the mica. Accordingly, the step of admixing the mica should be no more than about five minutes with the duration of the admixing step of less than about three minutes being even more preferred. Any suitable means may be used to carry out the sequential process in accordance with the invention, however, the process is  
5 normally carried out in a batch mode in a mixing chamber provided with a pair of rotating rotors in an apparatus referred to in the industry as a Banbury type mixer. One may choose to use a twin screw extruder or a Buss kneader to practice the inventive process if so desired, provided that appropriate elements are used to minimize shear heating.

10

In a further aspect of the invention, there is provided a process for making pottery-like, micronodular, low-odor microwaveable containers. The inventive process is generally directed to a process for forming a microwaveable, disposable, rigid and strong, mica and basic inorganic or organic compound filled  
15 polyolefin containers having food contact compatible olfactory properties, the polyolefin being selected from the group consisting of polypropylene and polypropylene polyethylene copolymer or blend, and a mixture of these wherein the inorganic or organic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate,  
20 aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, hydroxides of these elements, and mixtures of these organic compounds, mixtures of silicon dioxide with one or more of the  
25 following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the basic inorganic or organic compounds set forth herein. The process involves the steps of:

- 30 (a) forming an extrudable admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound;

- (b) extruding the extrudable admixture of the polyolefin resin, mica, and the basic inorganic compound or the basic organic compound at elevated temperature;
- (c) passing the resulting extruded admixture of the polyolefin resin and mica and the basic inorganic compound or the basic organic compound through a multiple roll stack, at least one roll of said stack having a matte finish;
- (d) thermoforming the extruded admixture of the polyolefin, resin, mica, and the basic inorganic compound or organic compound; and
- (e) recovering a container having a micronodular surface and exhibiting a melting point of no less than 250°F.

The container is dimensionally stable and resistant to grease, sugar, and water at temperatures up to about 220°F and has sufficient toughness to be resistant to cutting by serrated flatware. The amount of the basic inorganic compound or basic organic compound added is sufficient to reduce carbonyl moiety containing decomposition products to provide containers with suitable food contact compatible olfactory properties.

The process most preferably includes:

- (a) forming an extrudable admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound;
- (b) extruding the extrudable admixture of the polyolefin resin and mica and the basic inorganic compound or the basic organic compound at elevated temperature;
- (c) passing the resulting extruded admixture of the polyolefin resin and mica and the basic inorganic compound or the basic organic compound through a multiple roll stack, at least one roll of the stack having a matte finish;

(d) passing the extruded admixture of the polyolefin resin, mica, and basic inorganic compound or the basic organic compound at least partially around the roll having a matte finish;

(e) controlling the speed of the extrusion process, the size, temperature and configuration of the roll stack such that the surface of the extruded admixture of the polyolefin resin, mica, and the basic inorganic or organic compound not in contact with the matte roll has a coarse-grained structure;

(f) thermoforming the extruded admixture of the polyolefin, resin, mica, and the basic inorganic compound or organic compound; and

(g) recovering a container having a micronodular surface and a rough surface and exhibiting a melting point of no less than 250°F.

The coarse-grained structure of the surface of the extruded admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound not in contact with said matte roll is formed by transversing the extruded admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound through a curvilinear path and at least partially solidifying the surface of the extruded admixture of polyolefin resin, mica, and the basic inorganic compound or basic organic compound not contacting said matte roll while that surface is in tension relative to the surface contacting said matte roll. The container may be a plate, a cup, a bowl, a tray, a bucket, a soufflé dish or the like.

Thermoforming is typically conducted at a sheet temperature of from about 260° to about 310°F, and more preferably at a temperature of from about 280° to about 300°F.

There is provided in a still further aspect of the invention a crack-resistant, thermoformed food contact article having a wall thickness ranging from about 10 to about 80 mils consisting essentially of from about 40 to about 90 weight percent of a polypropylene polymer, from about 10 to about 50 percent by weight mica, from about 1 to about 15 percent by weight polyethylene, from about 0.1 to about 5 weight percent titanium dioxide and optionally including a basic organic or inorganic compound. The basic compound is, generally speaking, the reaction product of an alkali metal or alkaline earth element with carbonates, phosphates, carboxylic acids as well as alkali metal and alkaline earth element oxides, hydroxides, or silicates and basic metal oxides, including mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures thereof. A particularly preferred article is where the basic organic or inorganic compound is calcium carbonate which is present in an amount of from about 5 to about 20 weight percent.

15

Polyethylene is more typically present from about 2.5 to about 15 weight percent, preferably from about 4 to about 5 weight percent of the crack resistant article.

20

Titanium dioxide is included in various amounts, from about 0.1 to about 3 percent by weight being typical; from about 0.25 to 2 percent titanium dioxide may be included. Preferably, titanium dioxide is included in at least 0.5 percent by weight.

25

The caliper, or wall thickness, of the articles is usually from about 0.010 to about 0.050 inches or from about 10 mils to 50 mils. A caliper of from about 15 to 25 mils is most typically employed.

While any suitable polypropylene polymer may be employed, the most preferred polymer is isotactic polypropylene having a melt index in the range of from about 0.3 to 4, with a melt index of about 1.5 being typical. The

30

polyethylene employed may be HDPE, LLDPE, LDPE or MDPE, mixtures thereof or a polyethylene with bimodal molecular weight distribution.

Polypropylene is sometimes referred to hereafter as "PP".

5       The inventive compositions from which the crack resistant articles are made do not include coupling agents such as maleic anhydride containing polypropylene as further described herein, but may optionally include other components which do not alter the basic and novel characteristics of the crack-resistant plates. For example, nucleants such as sodium benzoate in amounts  
10       detrimental to crack resistance are to be avoided.

### **Brief Description of the Drawings**

15       The present invention will become more fully understood from the detailed description given herein below and the accompanying drawings, which are given by way of illustration only, and thus, are not limitative of the present invention and wherein:

Figure 1 is a schematic flow diagram of the sheet extrusion process;

20       Figure 2 is a schematic flow diagram of the thermoforming process for the manufacture of plates and containers having a micronodular surface;

Figure 3 is a chromatograph of a melt processed polypropylene/mica composition exhibiting relatively high odor;

Figure 4 is a chromatograph of a melt processed polypropylene/mica composition exhibiting relatively low odor;

25       Figure 5 is a plot of sensor responses vs. time for an automated aroma scanning device;

Figure 6 is a plot of the response integrals for the 32 sensors in an aroma scanning device for 3 different polypropylene/mica compositions;

Figure 7 is a schematic diagram of a Banbury type compounder;

30       Figure 8 is a plot of current draw vs. time for a compounding process according to the present invention in a compounder of the type shown in Figure 7:



Figure 9A is a scanning electron photomicrograph of a plate (upper picture) and Figure 9B is a scanning electron photomicrograph of a sheet (lower picture) of this invention wherein there is shown the micronodular food contact surface of the plate but not so for the neat extruded sheet;

5        Figure 10 is a graph plotting gloss versus mica level;

Figure 11 is a graph plotting the plate rigidity versus mica level;

Figure 12A is a scanning electron photomicrograph of a sheet of this invention showing a matted surface and Figure 12B is a scanning electron photomicrograph of a non-matted surface;

10       Figures 13A and 13B are scanning electron photomicrographs of sheets of this invention showing two high gloss sides;

Figures 14 A and B are isometric drawings of a plate of this invention;

Figures 15 A through C include cross sectional views of the plate shown in Figures 14 A and B;

15       Figure 16 is a radial cross-section of the plate shown in Figures 14 A and B;

Figure 17 is a schematic profile of the plate shown in Figures 14 A and B, beginning from the center line of the plate, formed in accordance with the present invention;

20       Figure 18 is a drawing of another plate of this invention;

Figure 19 is a cross sectional view of the plate shown in Figure 18;

Figure 20 is a schematic profile of the plate shown in Figure 18 beginning from the center line;

Figures 21A and 21B are drawings of a tray included in this invention;

25       Figures 22 A, B and C include a cross sectional view of the tray shown in Figures 21 A and B;

Figure 23 is a radial cross section of the tray shown in Figures 21A and B;

Figure 24 is a schematic profile of the tray shown in Figures 21A and B beginning from the center line;

30       Figures 25A and B are drawings of a bowl of this invention;

Figures 26A through C include a cross-sectional view of the bowl shown in Figures 25A and B;

Figure 27 is a radial cross section of the bowl shown in Figures 25A and B;

5 Figure 28 is a schematic profile of the bowl shown in Figures 25A and B beginning from the center line;

Figure 29 is a drawing of a take-out food container included in this invention;

Figures 30A and B are drawings of another bowl of this invention;

10 Figures 31A through 31C include a cross-sectional view of the bowl shown in Figures 30A and 30B;

Figure 32 is a radial cross section of the bowl shown in Figures 30A and 30B;

Figure 33 is a profile of the bowl shown in Figures 30A and 30B;

15 Figure 34 is a graph comparing the rigidity of the plates of this invention with prior art commercial products in the context of current material costs; and

Figure 35 is a bar graph comparing the heat resistance of the plates of this invention with prior art commercial products.

## 20 **Detailed Description of the Invention**

The aesthetically pleasing microwaveable disposable, rigid and strong containers including plates, bowls, cups, trays, buckets, soufflé dishes and lids comprise isotactic polypropylene, propylene-ethylene copolymer, or blends of  
25 isotactic polypropylene and propylene-ethylene copolymer coupled with a mixture of a platy inorganic mineral such as mica and basic inorganic or organic compounds which are the reaction product of an alkali metal or alkaline earth element with carbonates, hydroxides, phosphates, carboxylic acids, mixtures of silicon dioxide with one or more of the following oxides: magnesium oxide,  
30 calcium oxide, barium oxide, and mixtures of one or more of the basic organic or inorganic compounds set forth herein.

Suitably the basic inorganic or organic compounds are selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicon dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of these or other basic inorganic or organic compounds such as sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, and mixtures of these basic organic compounds.

The function of the basic inorganic compound or organic compound is to minimize the formation of odor-causing compounds in the mica/polyolefin composition and thus provide products with food contact compatible olfactory properties for consumer use. In this connection, the amount of the basic inorganic compound or organic compound added is controlled to be sufficient to reduce formation of decomposition products to sufficiently low levels to provide containers and plates with suitable food contact compatible olfactory properties. Suitably 5 to 15 weight percent of the container comprises the basic inorganic compound, advantageously about 8 to 12 percent. When the basic organic compounds are used, lower quantities are required, suitably from about 0.5 to 2.5 weight percent, advantageously 1.0 to 1.5 percent. Coupling agents and pigments may be utilized. Maleic anhydride and acrylic modified polypropylenes are suitable coupling agents for some embodiments.

25

The containers, bowls, trays and plates of this invention are preferably produced by compounding a suitable resin/mica composition; forming it into a sheet as shown in Figure 1 and then thermoforming the sheet as shown in Figure 2. These examples are illustrative and are not limitative of a preferred commercial process which involves in-line extrusion with regrind and thermoforming with multi-cavity mold beds.

30

Advantageously, the sheet is formed by an extrusion process utilizing the compounded polymer/mica basic inorganic compound or basic organic compound mixtures. The final extrusion process renders a sheet with excellent thermal properties, cut resistance, and food contact compatible olfactory properties. Generally, injection molding is inherently not suitable for the manufacture of self-texturized micronodular containers, bowls, trays and plates, since injection molded products are smooth plastic like articles which do not exhibit a micronodular surface or have the feel of stoneware or pottery-like look.

10

The aesthetically pleasing disposable microwaveable containers, trays, bowls and plates exhibit (a) food contact compatible olfactory properties, and (b) a melting point of at least 250°F. In addition, the container or plate is dimensionally stable and resistant to grease, sugar, and water at temperatures of up to about 220°F and are of sufficient toughness to be resistant to cutting by serrated polystyrene flatware. The preferred mica and basic inorganic compound or the basic organic compound filled polypropylene plates, besides exhibiting food contact compatible olfactory properties, exhibit on at least one side a micronodular surface and a thickness uniformity characterized by a thickness coefficient of variation (COV) of less than about five percent.

Mica is a common name for naturally occurring inert mineral of the phyllosilicate chemical family, specifically potassium aluminosilicate whereby the aluminum ions may be partially replaced by iron and magnesium and part of the chemically bound water may be substituted by fluorine.

Mica is easily cleaved into thin, relatively regular, flexible yet strong sheets (leaf-like flakes) with thickness in the range of half a micron and aspect ratio as high as 300. Mica is much softer than other inorganic fillers (wollastonite, glass) yet only slightly harder than talc. Mica has a slippery tactile feel and low abrasiveness relative to other common inorganic fillers.

The reinforcement effect at 40 weight percent mica is equivalent to that of 30 weight percent glass fiber. Hard inorganic fibrous fillers such as glass (various lengths) and wollastonite (acicular structures) have serious drawbacks such as abrasiveness and are prone to fracture degradation during conventional melt processing. Other fibrous (organic) fillers are derived from wood and vegetable sources and are not suitable for use in the manufacture of the containers of this invention since the organic fillers, when used in substantial amounts, tend to degrade during processing and they are also moisture sensitive. Preferably about 20 to 35 weight percent mica are used.

In some applications it may be preferred to treat the mica and/or basic inorganic compounds prior to using them in the inventive articles. A suitable compound for this treatment is amino-silane; sometimes referred to as a "coupling" agent.

Suitable basic inorganic and organic compounds used in the process include: calcium carbonate, sodium carbonate, sodium hydroxide, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicon dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of these or other basic inorganic or organic compounds such as sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, and mixtures of these basic compounds.

In the case where microwaveability is desired for a plastic disposable food contact article, the not so perfect solution has been the use of relatively expensive high heat modified polystyrene based or heat resistant materials (e.g., unfilled PPO and SMA engineering resins), where PPO refers to polyphenylene oxide and SMA refers to styrene-maleic anhydride copolymer.

The mica and basic inorganic compound or basic organic compound filled polypropylene containers, bowls, trays and plates of this invention have overcome the disadvantages of the prior art type containers, bowls, trays and plates and are significantly superior to them.

Mica and the basic inorganic compound or the basic organic compound filled polypropylene is compounded by pre-blending the polypropylene in pellet or flake form with mica powder and the basic inorganic compound or the basic organic compound powder and other additives (color concentrates, pigments, antioxidants, lubricants, nucleating agents, antistatic agents, etc.). This mixture is conveyed into the feed section addition point of a twin screw compounding extruder, or compounded in a Banbury-type mixer to provide a melt-processed polyolefin composition. Alternatively, the components are advantageously fed separately into the same or different points of addition, using combinations of volumetric and/or gravimetric (i.e., loss in weight type) feeders as further described herein.

For white pigmentation, titanium dioxide is preferred due to combination of brightness, and opacity, as well as stability during processing and final use. Surface treatment may be optionally used to further enhance wetting, dispersion, compatibility with matrix resins whereas the titanium dioxide forms may be of the rutile or anatase type. Alternate white pigments may also consist of calcined clay or blends of calcined clay with titanium dioxide. For black pigmentation, carbon black is preferred due to a combination of desirable characteristics such as blackness, and dispersibility, the latter of which can be carefully controlled by choice of particle size and surface chemistry. Carbon black is amorphous carbon in finely divided form which is made by either the incomplete combustion of natural gas (channel black) or by reduction of liquid hydrocarbons in refractory chambers (furnace black).

A twin screw extruder provides sufficient mixing action to effectively cause the wetting and dispersion of the filler into the polymer matrix. The twin screw extruder may be of the co-rotating or counter-rotating type, where each type is equipped with different screw flight elements which are appropriate for the feed, mixing, and melt metering zones. The discharge zone normally consists of a strand die where the exiting molten material strands are quenched in a circulating water bath followed by knife cutting into pellets. In a particularly preferred embodiment, a Banbury-type mixer is used for compounding the resin, mica and basic compound as further described herein.

10

Low molecular weight additives such as waxes, fluorinated polymers, and other specialty lubricants are suitably used as process aids to reduce the melt viscosity and improve throughput. Polyethylene resin may also be added to the blend. Other additives may include nucleating agents and antistatic agents.

15 Antioxidants may be added in small amounts, generally less than one weight percent, to minimize shear and thermal degradation of the polypropylene during the extrusion and forming processes as well as to promote the chemical stability of the sheet prior to and during final article use. Suitable antioxidants are advantageously selected from the group of phenolics and phosphites and blends thereof. These are produced by Ciba-Geigy and General Electric Corporation.

20

Plastic sheet extrusion equipment is suitable for the manufacture of multilayered or single layered mica and the basic inorganic or organic compound filled sheets of a polyolefin selected from the group consisting of polypropylene, polypropylene/polyethylene copolymer or blend, and mixtures of these. Melt strength of the sheets is improved when mica is used as a filler since geometry of the mineral in the form of high aspect ratio flakes serves to provide "inter-particle connectivity" or physical cross-linking. The food contact compatible olfactory properties are enhanced when in addition to the mica, basic inorganic compounds or organic compounds such as calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium

25

30

borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicon dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of these or other basic inorganic or organic compounds such as sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, and mixtures of these are mixed with mica and the polyolefin to produce the containers of this invention.

In Figure 1 a process is shown for the manufacture of a single layer mica filled polypropylene sheet or polypropylene filled with mica and basic inorganic compounds or organic compounds set forth hereinabove. Previously compounded and pelletized mixtures of polypropylene, mica and the basic inorganic compound or organic compound, and other additives are gravity fed by a hopper 10 into the feed zone of a single screw extruder system. Primary extruder 11 has a 2 inch diameter screw with a 24/1 length to diameter ratio. Optionally multilayer coextruded sheet can be produced by utilizing at least one additional single screw extruder 12,13,14 in conjunction with a combining feedblock with proper melt piping and manifold arrangements. Suitably one to seven screw extruders are employed, preferably three. A flexible lip flat sheet die 15 having a width of 31 inches was used.

The sheet of this invention 16 enters the sheet takeoff portion (i.e., after the molten material exits the die) comprising a three-roll polishing/casting unit 17 with individually temperature controlled rolls, a two-rubber roll sheet pull unit 18, and a dual turret, dual shaft winder, whereby only one shaft winder roll 19 may be used. The three takeoff units were mechanically tied together, were on a common track, and can be automatically traversed from close die lip proximity to about 36 inch distant. During the extrusion process, the distance between the die exit and the casting unit was maintained at 2 inches. These three chrome rolls comprising the sheet casting unit are individually temperature controlled by integral oil circulating pumps and heat exchangers. Nip gaps are adjustable. A



speed differential between cast rolls and pull rolls is normally maintained such that pull roll speed is approximately within ten percent (10%) of cast roll speed. On a pilot line, achievable line speeds are in the range of 1-12.5 feet per minute; while for a sheet on the order of 20 mil thick, the line speed is about 5-6 feet per minute. The sheet is wound on a roll. Table 1 shows the sheet process conditions employed for the sheet extrusion of mica and basic inorganic compound or the basic organic compound filled polypropylene and the unfilled polypropylene control. In a commercial operation, the speed is increased by a factor of 10 to 20 times.

10

Thermoforming is the pressing or squeezing of pliable material into final shape. In the simplest form, thermoforming is the draping of a softened sheet over a shaped mold. In the more advanced form, thermoforming is the automatic, high speed positioning of a sheet having an accurately controlled temperature into a pneumatically actuated forming station whereby the article's shape is defined by the mold, followed by trimming and regrind collection.

Forming techniques other than conventional thermoforming are also suitable for the manufacture of articles described in the present invention. These include variations such as presoftening the extruded sheet to temperatures below the final melting temperature, cutting flat regions (i.e., blanks) from the sheet, transfer of blanks by gravity or mechanical means into matched molds whereby the blanks are shaped into the article by heat and pressure. The sheet from which the blanks have been cut out is collected as regrind and is recyclable. Conventional paperboard pressing equipment and corresponding forming tooling is optionally modified to produce articles of this invention.

The extruded sheet used in a preferred thermoforming process as shown in Figure 2 has a thickness of about 0.010 to 0.080 inches (10 to 80 mils), suitably 0.010 to 0.050 inches. For the plates the preferred thickness is about 0.015 to 0.025 inches. Suitable mica filler loading level in the extruded sheet is in the

range of 10 to 50 weight percent, more preferably 20-50 weight percent and most preferably 20-35 weight percent. To achieve suitable food contact compatible olfactory properties, the basic inorganic compound loading level should be 5 to 15 weight percent, advantageously 8 to 12 weight percent. For the basic organic  
5 compound the loading levels should be 0.5 to 2.5 weight percent, preferably 1.0 to 1.5 weight percent. The mica flake aspect ratio is in the range of 30-300, more preferably 15-250, with particle size range of about 10-500 microns. The extruded sheet comprises isotactic polypropylene homopolymer or polypropylene polyethylene copolymer or blend or a mixture of these as base resin, preferably  
10 having a melt flow index in the range from about 0.3 to about 4.0, more preferably 0.5 - 2.0 and most preferably about 1.5. Propylene copolymers or blends with ethylene levels in the range of 1-10 mole percent, more preferably 2-5 mole percent, are optionally used.

15 The preferred type of mica is muscovite, which is the most common form in commerce. Optionally other less common mica types such as phlogopite, biotite and fluorphlogopite are used. Although there are an infinite number of compositions possible for these four generic types due to isomorphous substitution which are mine specific, the selection of particular grades is driven by particle  
20 aspect ratio, particle size, price and availability.

Suitably the extruded sheet includes coloring agents for aesthetic appeal, preferably titanium dioxide, carbon black, and other opacifying agents in the range of 0.5-8 weight percent based on total composition, preferably 1.5 to 6.5  
25 weight percent. The extruded sheet comprises minor amounts of other additives such as lubricants and antioxidants. These articles of manufacture may be suitably colored with pigments or dyes. Pigments are defined as small insoluble organic or inorganic particles dispersed in the resin medium to promote opacity or translucency. Usual pigments include carbon black, titanium dioxide, zinc oxide,  
30 iron oxides, and mixed metal oxides. Dyes are organic and soluble in the plastic, and may be used alone or in combination with pigments to brighten up pigment

based colors. All such colorants may be used in a variety of modes which include dry color, conventional color concentrates, liquid color and precolored resin.

Mica and the basic inorganic compound or the basic organic compound  
5 filled polypropylene sheets are suitably formed into plates, bowls, cups, trays, buckets, soufflé dishes, and containers using a forming or thermoforming process disclosed herein. In a pilot process, these articles of manufacture and containers may be made using the Comet Starlett thermoformer unit. This machine is capable of vacuum forming products from heat softened thermoplastic materials  
10 and is schematically depicted in Figure 2. Sheet portions 23 having dimensions of 17.5 inches by 16.25 inches were clamped on two opposing sides and inserted into an oven indicated at 22 equipped with upper 20 and lower 21 heaters, whereby heater input settings were in the range of 20-30 percent and hold times were on the order of 60-80 seconds. Under these conditions, the oven air temperature as  
15 recorded by a digital thermocouple was in the range of 221°F to 225°F, while the sheet surface temperature, as recorded by adhering indicator thermocouples, was approximately 330°F to 340°F.

When the clamped and heat softened sheet 23 exits the oven 22, it may be  
20 vacuum formed by either procedure (A) or (B) in a commercial process. Both methods utilize only one mold which is suitably fabricated from epoxy thermoset materials or suitable mold materials including aluminum, steel, beryllium, copper and the like. Mode (A) uses a male mold 24 whereby the sheet is sucked up to conform to it by means of vacuum where the vacuum ports are present on the  
25 mold base as well as on the periphery side of the container (i.e., flange area). Mode (B) arrangement is such that the vacuum direction is opposite to mode (A), where again vacuum holes are located around the base and periphery. In the case of mode (B), a female mold 25 is used, and this arrangement is preferred since the air side of the sheet corresponds to the food contact side. In mode (B) the food  
30 contact side undergoes a beneficial texturizing effect as a result of the heat treatment, whereby the resin flows around and outward from the mica particles

close to the surface causing the mineral to become more exposed which creates a micronodular surface as manifested by decreased gloss and increased surface roughness. The micronodular surface gives the container a stoneware or pottery-like appearance.

5

Suitably a process for forming a disposable, microwaveable, rigid and strong

mica and the basic inorganic compound or the basic organic compound filled polyolefin container, plate, bucket, or the like, having food contact compatible,

10 olfactory properties wherein the polyolefin is selected from polypropylene, polypropylene polyethylene copolymer or blend and the basic inorganic

compound and the basic organic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate,

aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide,

15 strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicon dioxide with one or more of the

following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of these or other basic inorganic or organic compounds such as sodium stearate,

calcium stearate, potassium stearate, sodium citrate, potassium citrate and

20 mixtures of these comprise the steps of:

(a) forming an extrudable admixture of the polyolefin resin, mica, and the basic inorganic compound or the basic organic compound;

25 (b) extruding said extrudable admixture of the polyolefin resin, mica and the basic inorganic compound or the basic organic compound at elevated temperature;

(c) passing the resulting extruded admixture of the polyolefin resin, mica and the basic inorganic compound or the basic organic compound through a multiple roll stack, at least one roll of said stack having a matte finish;

30

- (d) passing said extruded admixture of the polyolefin resin and mica and the basic inorganic compound or the basic organic compound at least partially around said roll having a matte finish;
- 5 (e) controlling the speed of said extrusion process, the size, temperature and configuration of said roll stack such that the surface of said extruded admixture of polyolefin resin, mica and the basic inorganic compound or the basic organic compound not in contact with said matte roll has a coarse-grained structure; and
- 10 (f) thermoforming said extruded admixture of polyolefin, mica and the basic inorganic compound or the basic organic compound and recovering a container, plate, bucket, or the like, having a micronodular surface and a rough surface, exhibiting a melting point of no less than about 250°F; the container, plate, bucket, etc., being dimensionally stable and resistant to grease, sugar and water at temperatures up to about 220°F and having sufficient toughness to be resistant to cutting by serrated flatware and exhibiting food
- 15 contact compatible olfactory properties.
- 20

Advantageously, the coarse-grained structure of the surface of said extruded admixture of polyolefin resin, mica and the basic inorganic compound or the basic organic compound not in contact with said matte roll is formed by

25 transversing the extruded admixture of the polyolefin resin, mica and the basic inorganic compound or the basic organic compound through a curvilinear path and at least partially solidifying the surface of said extruded admixture of polyolefin resin, mica and the basic inorganic compound or the basic organic compound not contacting said matte roll while that surface is in tension relative to

30 the surface contacting the matte roll.

Generally, a process for forming a mica basic inorganic compound or basic organic compound filled polypropylene container, plate, bucket, tray, bowl, or the like, comprises the steps of:

- 5 (a) forming an extrudable admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound;
- (b) extruding said extrudable admixture of the polypropylene resin, mica and the basic inorganic compound or the basic  
10 organic compound at elevated temperature;
- (c) passing the resulting extruded admixture of the polypropylene resin, mica and the basic inorganic or the basic organic compound through a multiple roll stack, at  
15 least one roll of said roll stack having a matte finish;
- (d) passing said extruded admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound at least partially around said roll having a matte finish;
- 20 (e) controlling the speed of said extrusion process, the size, temperature and configuration of said roll stack such that the surface of said extruded admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound in contact with said matte roll has a matted structure; and
- 25 (f) thermoforming said extruded admixture of polypropylene resin, the mica and the basic inorganic compound or the basic organic compound, and recovering a container, plate, bucket, or the like having a micronodular surface and exhibiting a melting point of no less than 250°F, the  
30 container, plate, bucket, or the like being dimensionally stable and resistant to grease, sugar and water at

temperatures up to about 220°F and having sufficient toughness to be resistant to cutting by serrated flatware and further exhibiting food contact compatible olfactory properties.

5

A process for forming a mica and the basic inorganic compound or the basic organic compound filled polypropylene sheet suitable for thermoforming micronodular containers and plates comprises the steps of:

10

(a) forming an extrudable admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound;

15

(b) extruding said extrudable admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound at elevated temperature;

20

(c) passing the resulting extruded admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound through a multiple roll stack, at least one roll of said roll stack having a matte finish;

25

(d) passing said extruded admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound at least partially around said roll having a matte finish;

30

(e) controlling the speed of said extrusion process, the size, temperature and configuration of said roll stack such that the surface of said extruded admixture of the polypropylene resin, mica and the basic inorganic compound or the basic organic compound not in contact with said matte roll has a coarse structure; and

(f) the surface in contact with the matte roll has a matte surface; and

- (g) recovering a sheet having a matted surface and a coarse surface, said sheet comprising polypropylene, mica and the basic inorganic compound or the basic organic compound moieties. The sheet has food contact compatible olfactory properties.

5

Advantageously, other thermoforming arrangements are suitable and may be preferred in conventional sheet and web feed thermoforming commercial production operations. Alternative arrangements include the use of drape,  
10 vacuum, pressure, free blowing, matched die, billow drape, vacuum snap-back, billow vacuum, plug assist vacuum, plug assist pressure, pressure reverse draw with plug assist vacuum, reverse draw with plug assist, pressure bubble immersion, trapped sheet, slip, diaphragm, twin-sheet cut sheet, twin-sheet rollfed forming or any suitable combinations of the above. Details are provided in J.L.  
15 Throne's book, Thermoforming, published in 1987 by Coulthard. Pages 21 through 29 of that book are incorporated herein by reference. Suitable alternate arrangements also include a pillow forming technique which creates a positive air pressure between two heat softened sheets to inflate them against a clamped male/female mold system to produce a hollow product. Metal molds are etched  
20 with patterns ranging from fine to coarse in order to simulate a natural or grain like textured look. Suitably formed articles are trimmed in line with a cutting die and regrind is optionally reused since the material is thermoplastic in nature. Other arrangements for productivity enhancements include the simultaneous forming of multiple articles with multiple dies in order to maximize throughput  
25 and minimize scrap.

Various measurements used herein include melt flow index, SSI rigidity (sometimes referred to below as simply "rigidity"), Parker Roughness and so forth. Unless otherwise indicated explicitly or by context, these terms have the  
30 meaning set forth below.



The melt flow rate (MFR) or melt index is a common and simple method for determining the flow properties of molten polymers. (As used herein, ASTM D 1238-95, Condition 230/2.16). Resin is introduced and melted in a cylindrical space. After temperature equilibration is reached, a weight is used to push a  
5 plunger vertically downward whereby the resin is extruded through a narrow orifice. The usual test temperature and the temperature utilized herein for polypropylene is 230°C and the load is 2.16 Kg. Extruded material is collected and weighed and the time required to extrude a specific weight is recorded. MFR or melt index is expressed as grams per minutes, or grams per 10 minutes, which  
10 is the weight of material extruded in a 10 minute time period. MFR is inversely proportional to both polymer viscosity and polymer molecular weight.

SSI rigidity is measured with the Single Service Institute Plate Rigidity Tester originally available through Single Service Institute, 1025 Connecticut  
15 Ave., NW. Washington, D.C. The SSI Rigidity test apparatus has been manufactured and sold through Sherwood Tool, Inc., Kensington, CT. This test is designed to measure the rigidity (i.e. resistance to buckling and bending) of paper and plastic plates, bowls, dishes, and trays by measuring the force required to deflect the rim of these products a distance of 0.5 inch while the product is  
20 supported at its geometric center. Specifically, the plate specimen is restrained by an adjustable bar on one side and is center fulcrum supported. The rim or flange side opposite to the restrained side is subjected to 0.5 inch deflection by means of a motorized cam assembly equipped with a load cell, and the force (grams) is recorded. SSI rigidity is expressed as grams per 0.5 inch deflection. A higher SSI  
25 value is desirable since this indicates a more rigid product. All measurements were done at room temperature and geometric mean averages for the machine and cross machine direction are reported.

The Parker Roughness method was used to determine roughness using the  
30 Messmer Parker Print-Surf Roughness. Operation procedure details are referenced in the Messmer Instruments Ltd. User manual for the instrument

(Model No. ME-90) which is distributed by Huygen Corporation. The flat specimen is clamped under 1 Mpa pressure against a narrow annular surface by a soft backing and the resistance of air flow of the gap between the specimen and the annulus is measured. The air flow is proportional to the cube of the gap width and the roughness is expressed as the root mean cube gap in units of micrometers. Higher Parker roughness values indicate higher degrees of surface roughness.

Gloss is reported as "gloss units at 75 or 60 degrees." Gloss measurements were conducted following TAPPI Standard Method T-480-OM 92.

The following examples are illustrative of the present invention. It should be understood that the examples are not intended to limit the invention and that various modifications may be made by those skilled in the art without changing the essential characteristics of the invention.

#### Examples 1 - 8

Mica filled polypropylene sheets (20 mil) and unfilled polypropylene sheets (22 mil) were extruded, as shown and described in connection with in Figure 1, with conditions specified in Table 1. These extrusion process conditions may be varied as necessary to produce sheets which are of acceptable quality. Specifically, the operable temperature ranges for barrel zones 1,2, and 3 are about respectively, 350 to 425°F, and 450 to 500°F. the adaptor, feedblock, and die temperatures can all be in about the range of 450 to 500°F. the range of values for extruder drive amperes, extruder speed, melt pressure, die pressure, chill roll temperature, and line speed are about respectively, 12 to 20 amp., 60 to 100 RPM, 1500 to 2500 psi, 450 to 650 psi, 120 to 140°F, and 3 to 8 FPM. Sheets are subsequently vacuum thermoformed into plates and other containers and lids as set forth in Figures 14 through 33. There is reported in Tables 2 and 3, respectively, rigidity values and caliper data for the sidewall, bottom, and flange (rim) areas of vacuum formed plates using condition (B) of Figure 2 and having a

diameter of 10.25 inches. In each table, individual rigidity values are shown for each specimen. In addition, the caliper uniformity for sidewall, bottom, and flange areas are reported for each specimen, along with the summary statistics. Specifically, the caliper of each plate specimen in Tables 2 and 3 was measured  
5 ten times using a Fowler gauge for each of the three regions of interest consisting of the sidewall, bottom, and flange areas, and the average value for each plate specimen is reported along with the corresponding standard deviation in thousands of inches or mils (i.e., individual plate statistics). In the case of the three plates of Table 2, the caliper summary statistics (expressed in the average properties row)  
10 were obtained on the basis of averaging 30 measurements, wherein the standard deviation is reported for each of the three regions of interest. In the case of the five plates of Table 3, the caliper summary statistics were calculated on the basis of averaging 50 measurements where again the standard deviation is reported for each of the three regions of interest. Therefore, the caliper data of Tables 2 and 3  
15 located in the average property rows pertain to global statistics rather than individual plate statistics. The caliper uniformity parameter consists of the coefficient of variation (COV) which is calculated as the standard deviation of caliper divided by the mean caliper, whereas the ratio is multiplied by 100, whereas the above described global averages and associated standard deviations  
20 are employed. A lower COV value is desirable since it signifies improved caliper uniformity for mica filled polypropylene plates with respect to unfilled polypropylene plates. Tables 2 and 3 show that mica reduces COV of polypropylene from 9.9 to 4.3 in sidewall and from 9.6 to 2.0 in the flange area. Therefore, caliper uniformity in sidewall improved by more than a factor of 2 and  
25 caliper uniformity in the flange improved by over a factor of 4. The improvement of caliper uniformity is critical for promoting plate dimensional stability during food transport and microwave cooking operations. In great contrast to mica filled polypropylene plates, the unfilled polypropylene plates exhibited poor quality as evidenced by poorly defined rim area, and sharkskin, very rough surface. These  
30 data demonstrate that mica greatly improves the drawability of polypropylene as evidenced by improved caliper uniformity, as well as improved

thermoformability, both of which are due to enhanced melt strength relative to unfilled polypropylene. Mica is the preferred reinforcing mineral filler for enhancing the melt strength because of its highly regular, high aspect ratio morphology which can be thought of as resulting in "inter-particle connectivity" or "physical cross-linking". The significant reinforcing effect of mica is also evidenced by a SSI plate rigidity value of 671 grams per 0.5 inches for PP/mica at a basis weight of about 350 lbs. per square foot ream versus 342 grams per 0.5 inches for unfilled PP at a basis weight of about 280 lbs. per 3000 square foot ream.

10

**Table 1**

Sheet Extrusion Conditions for Mica Filled Polypropylene and Unfilled Polypropylene		
CONDITION	PP/MICA	UNFILLED PP
Barrel Zone 1 (°F)	395	395
Barrel Zone 2 (°F)	425	425
Barrel Zone 3 (°F)	475	475
Adaptor (°F)	470	450
Feed block (°F)	470	460
Die Zones 1-3 (°F)	470	475
Extruder RPM	80	70
Drive amperes	16	19
Melt pressure (psi)	1700	1780
Die pressure (psi)	550	825
Line speed (FPM)	6.1	5.0
Chill roll temp. (°F)	130	137

**Table 2**

Caliper and Rigidity Data for 10-1/4 Inch Plates Thermoformed From Unfilled Polypropylene Sheet				
Plate Specimen Example	Rigidity (g/0.5 in.)	Sidewall Caliper (mil)	Bottom Caliper (mil)	Flange Caliper (mil)
1	364	18.7 ± 1.9	20.7 ± 0.8	22.9 ± 2.8
COV*		10.1	3.9	12.2
2	382	19.2 ± 20.	20.6 ± 0.4	23.3 ± 0.8
COV		10.4	1.9	3.4
3	280	19.6 ± 1.9	20.6 ± 0.5	23.3 ± 2.8
COV		9.7	2.4	12.0
Average Properties	342 ± 54.4	19.19 ± 1.89	20.64 ± 0.58	23.15 ± 2.21
COV		9.85	2.81	9.55

COV = Coefficient of Variation

**Table 3**

Caliper and Rigidity Data for 10-1/4 inch Plates Thermoformed From Polypropylene/Mica/TiO <sub>2</sub> Sheet				
Plate Specimen Example	Rigidity (g/0.5 in.)	Sidewall Caliper (mil)	Bottom Caliper (mil)	Flange Caliper (mil)
4	705	18.3 ± 1.1	17.4 ± .05	18.2 ± 1.0
COV *		6.0	2.9	5.5
5	659	17.0 ± 1.5	17.9 ± 0.7	18.4 ± 0.5
COV		8.8	3.9	2.7
6	654	17.3 ± 1.6	17.0 ± 0.6	18.2 ± 0.7
COV		9.2	3.5	3.8
7	669	16.9 ± 1.2	16.7 ± 1.1	18.9 ± 0.8
COV		7.1	6.6	4.2
8	668	16.3 ± 1.0	16.3 ± 0.9	19.0 ± 0.9
COV		6.1	5.5	4.7
Average Properties	671 ± 20	17.3 ± 0.76	17.1 ± 0.6	18.5 ± 0.38
COV		4.3	3.5	2.0

COV = Coefficient of Variation

**Examples 9-11**

Thirty percent mica and ten percent calcium carbonate filled polypropylene sheet was run on a commercial extrusion line. The extruder was a  
5 6" Egan single screw with an EDI flex lip die. In these Examples 9 - 11, the resulting melt temperature was approximately 400°F and the temperature for Barrel Zones 1-5 were approximately 400/396, 390/390, 370/370, 370/370, and 370/371 as shown in Table 4.

10 Lower melt temperatures are typically preferred. Process melt temperatures of 370°F or so will help control undesirable odors in the product. Process melt temperature as used throughout refers to a measured value of the temperature of a composition when the polypropylene is molten and unless otherwise stated, is indicative of the maximum temperature of a particular step.

15

For the runs reported in Table 4, an auger feeder was installed just above the feed throat of the extruder to introduce color concentrates for producing green, blue, and eggshell colored sheet. The concentrate was added at levels between 1% - 5%.

**Table 4**

Extrusion Conditions for 30% Mica/10% Calcium Carbonate Filled Polypropylene

Set/Actual Conditions			
	Green	Blue	Eggshell
Barrel Zone 1 Temp (F)	400/396	400/398	400/399
Barrel Zone 2 Temp (F)	390/390	390/390	390/391
Barrel Zone 3 Temp (F)	370/370	370/370	370/370
Barrel Zone 4 Temp (F)	370/370	370/370	370/370
Barrel Zone 5 Temp (F)	370/371	370/370	370/370
Adaptor Temp (F)	370	370	370
Melt Temp (F)	400	400-405	404/405
Die Zone 1 Temp (F)	380	385	385
Die Zone 2 Temp (F)	370	370	370
Die Zone 3 Temp (F)	370	370	370
Die Zone 4 Temp (F)	370	370	370
Die Zone 5 Temp (F)	380	385	385
Screw RPM	30	30	30
Drive Amperes	325-345	335-352	347-350
Screen Pack	20 mesh	20 mesh	20 mesh
Back Pressure (psi)	2350-2510	2370-2600	2515-2680
Line Speed (fpm)	30/28/20	30/28/22	27/26/20
Throughput (lb./hr.)	725	725	725
Top Stack Roll Temp (F)	120-130	120-130	120-130
Middle Stack Roll Temp (F)	120-130	120-130	120-130
Bottom Stack Roll Temp (F)	120-130	120-130	120-130
Roll Gap - top (mil)	17	17	17
Roll Gap - bottom (mil)	23	23	23
Nip Roll Pressure	50	80	80
Die Gap (mil)	15 middle - 30 edges	15 middle - 30 edges	15 middle - 30 edges
Die - Full Width (in)	52	52	52
Die to Nip Distance (in)	Approximately 4.5	Approximately 4.5	Approximately 4.5
Sheet Width (in)	51.5	51.5	51.5
Sheet Caliper (mil)	17.5/18.5/24	17.5/18.5/24	17.5/18/24
Color Auger Setting (%)	4	4	1
Trim Regrind Used	Yes	Yes	No
Footage Produced	12000	11000	15000



**Examples 12 - 17****Aroma Profile Test Method**

5       The Sensory Analysis Center at Kansas State University has developed a  
profiling protocol in which a highly trained panel identifies specific odors and  
rates their intensity. The intensity scale is a 15-point "universal" scale of the type  
typically chosen for sensory studies, where 1 is barely perceptible or threshold and  
15 is extremely strong. If an attribute or odor component is not listed in the tables  
10       which follow, it means it is not present and would score a 0. The panel members  
are selected on the basis of a series of screening tests that include basic taste, odor  
recognition, taste intensity recognition, taste intensity ranking, and a personal  
interview to evaluate availability and personality traits. Training, which includes  
the fundamental sensory principles and all aspects of the profile technique, is done  
15       over a 4-12 month period.

The panelists work as a group to arrive at a description of the product.  
Individual results are compiled by the panel leader and discussion follows in  
which disagreements are discussed until a consensus is reached on each  
20       component of the profile. Reference materials and more than one session usually  
are required in order to reach the consensus.

The procedure for resin is to place 40 ml. of resin in a 340 ml. glass brandy  
snifter, which is covered with a watch glass. Sheet samples are cut into two 2" x  
25       2" sections and placed in the same size brandy snifter. In testing, panelists found  
that some samples had initial odor components that disappeared rapidly.  
Therefore an initial impact and a sustained impact were evaluated for each  
sample. The initial impact was judged immediately after the watch glass had been  
removed; the sustained impact was judged 10 seconds after the watch glass had  
30       been removed. Typical results are shown in the Table 5 below for Low Odor and  
High Odor Compositions. "Low" odor formulations were produced using lower

melt processing temperatures in compounding and adding 10% calcium carbonate to the formulation. The sheets were prepared as shown and described in connection with Examples 1 through 11.

**Table 5**  
**High Odor vs. Low Odor Polypropylene Composites:**  
**Effect of Adding 10% CaCO<sub>3</sub>**  
**ODOR PROFILE FOR COMPOUNDED RESIN**

Resin Impact		Consensus Odor Profile on Resin (Kansas State University Sensory Analysis Center)									
		Initial	Sustained	Petroleum	Pungent	Musty	Scorched	Medicinal	Sweet	Waxy	Soapy
High Odor		9.0	3.5	8.0	4.0	7.0	3.5	3.0			
Low Odor		5.5	2.5	2.5		4.5			1.5	2.0	4.5

High Odor Resin		Low Odor Resin	
65.63%	Polypropylene	55.63%	Polypropylene
30 %	Mica	30 %	Mica
2.5 %	Coupling Agent	10 %	CaCO <sub>3</sub>
1.87 %	Pigment	2.5 %	Coupling Agent
		1.87 %	Pigment

High Odor and Low Odor compositions were compounded utilizing the process melt temperatures indicated in the first column of Table 6 and formed into sheets as described above. Both resin and sheet were evaluated for aroma profile.

Table 6

**ODOR PROFILE FOR SHEET FORMED  
FROM COMPOUNDED RESIN AT TWO TEMPERATURES**

Sheet Impact			Consensus Odor Profile on Sheet							
Resin	Initial	Sustained	Petroleum	Pungent	Musty	Scorebed	Medicinal	Sweet	Waxy	Soapy
High Odor 370°F	12.0	6.0	10.0	8.0	7.5	4.5	4.0			
High Odor 459°F	11.0	8.0	7.5	7.5	6.0	3.5	2.0			
Low Odor 371°F	5.5	2.0	3.5		4.0			2.0	2.5	
Low Odor 460°F	5.5	2.0	3.0		3.5			2.0		3.5

The foregoing data demonstrates that: when a basic moiety containing compound was added to the mica polyolefin composition, a resin was produced having suitable food contact compatible olfactory properties. Significant decreases in the initial and sustained odors were observed and the scorched, pungent, and petroleum aroma components were removed or greatly reduced and these undesirable components seem to be replaced with sweet, waxy, and soapy aroma components.

When compounded pellets are subjected to sheet extrusion, those without calcium carbonate increase in the disagreeable components (pungent and petroleum) and increase in the initial and sustained odor output with subsequent processing. In contrast, when pellets contain calcium carbonate, no increase in undesirable aroma components was observed and no increase in the initial or sustained odor was produced with subsequent processing. Test panel data correlated well with analytical techniques as can be seen from the discussion and examples which follow.

### C8/C9 Ketones

The precise nature of the odor causing compounds in polypropylene/mica compositions is not known; however, it has been found that undesirable odors correlate well with eight carbon (C8) and nine carbon (C9) alkyl ketones as described hereinafter, and may be associated with such compounds.

A Likens-Nickerson steam/methylene chloride extraction technique was used to extract possible odor causing compounds from polypropylene/mica compositions and produce a concentrate. The extraction was performed until complete. The concentrate was analyzed through gas chromatography/mass spectrometry to produce chromatograms such as those shown in Figures 3 and 4. The abscissa is an arbitrary time scale, while the ordinate is an arbitrary abundance scale. The peak for alkyl C<sup>o</sup> (labeled as A) ketone assigned to be 4-

5 methyl-2-heptanone, appears on both Figures 3 and 4 at slightly above 16.8 on the time scale as indicated; while the peak for C9 alkyl ketone (labeled as B), assigned to be 4,6-dimethyl-2-heptanone appears slightly below 17.6 on the time scale in both chromatograms. Other peaks of interest on Figures 3 and 4 are C7 ketones at slightly above 15.1, 15.6 and 16.3 on the abscissa. The peaks are respectively assigned to be 2-heptanone, 3-heptanone and 4-heptanone. They are respectively labeled as C, D and E. There is also shown on both Figures 3 and 4 peaks for what are to be assigned to be various C7 alcohols at about 18, 18.2 and 18.8 on the abscissa. These compounds are respectively labeled as F, G and H on the diagrams and are assigned to be 2-heptanol, 3-heptanol, and 4-heptanol. The C8/C7 ratios referred to hereinafter are ratios of the abundance at the peaks assigned to be 4-methyl-2-heptanone to the abundance at the peak assigned to be 4-heptanone as measured by Likens-Nickerson extraction followed by gas chromatography/mass spectrometry. That is, the C8/C7 ratio for a given sample is the ratio of peak intensity (height) of peak A to the peak intensity of peak E. Similarly, the C9/C7 ratio is the ratio of the peak intensity of peak B to the peak intensity of peak E in Figures 3 and 4 for a given sample.

20 Figure 3 is a chromatogram characteristic of extruded pellets having a relatively strong odor wherein the C8 and C9 ketones indicated each have an extractable concentration of about 10 parts per million parts by weight in the product. Figure 4 is a chromatogram characteristic of relatively "low odor" extruded pellets substantially free of C8 and C9 ketones as shown. Generally, "low odor" compositions reduce concentration of C8 and C9 ketones over "high odor" compositions by 2/3 with 1/5 being typical and 1/10 being preferred. Thus, in general, melt compounded compositions in accordance with the invention have extractable concentrations of C8 and C9 alkyl ketones of less than about 3.5 ppm (weight) with less than 2 ppm being typical and less than 1 ppm being particularly preferred.

It can also be seen from the chromatograms in Figures 3 and 4 that the adjacent C7 ketone levels are comparable in both the "low odor" and "high odor" compositions. Thus, the C8/C7 ratio can be used as an alternative indicator of desirable olfactory characteristics. Typically, "low odor" compositions in accordance with the invention have a C8/C7 ratio at least five times less than high odor compositions with at least ten times less being typical.

In preferred compositions according to the invention, C8/C7 ratios as measured by Likens-Nickerson extraction followed by gas chromatography/mass spectrometry are generally less than about 0.5 or so as is seen from in the examples which follow. C8/C7 ratios of less than about 0.3 are typical and C8/C7 ratios of less than about 0.1 are particularly preferred. The articles of the invention and the pellets from which they are made are further characterized by a relative aroma intensity index which is determined by commercially available equipment in accordance with the procedure detailed below.

#### Relative Aroma Intensity Index

Melt processed compositions produced in accordance with the present invention, particularly extruded pellets from which articles such as plates and bowls are made, characteristically exhibit relatively low odor as opposed to conventionally formulated mica/polypropylene compositions. Generally the relative aroma intensity index (as defined herein) is less than about 1.6, with less than or equal to about 1 being preferred. In general, the lower the relative aroma intensity index, the lower the odor intensity of the mica/polypropylene pellets. Less than or equal to about 0.7 is most preferred with a practical lower limit believed to be somewhere around 0.1 or so. Thus, in accordance with the invention, melt compositions will generally have a relative aroma intensity index of less than about 1.6 and typically from about 1.5 to about 0.1. Within the range



of from about 1.0 to about 0.1 is more typical, while a relative aroma intensity index of from about 0.7 to about 0.1 is preferred.

The relative aroma intensity index (RAII) of a particular melt-processed composition is readily determined using conventional materials and equipment.

The relative aroma intensity index is defined as the arithmetic average of all sensor integrals for a given sample divided by the arithmetic average of all sensor integrals for a standard sample specified below; or in equation form:

10

$$\text{RAII} = \frac{\text{Arithmetic Average of Odor Intensity over all sensors of sample}}{\text{Arithmetic Average of Odor Intensity over all sensors of standard composition}}$$

15

A commercially available aroma scanning device is used. Typically, such devices utilize a plurality of conductivity sensors to determine the odor of a sample. The particular device used in the discussion which follows uses 32 sensors whose response is integrated over time. The various integrals are arithmetically averaged for each sample (or standard composition as the case may be). This arithmetic average is then used in both the numerator or the denominator in the above noted equation.

The standard composition utilized for determining RAII herein is produced from the following components:

25

**Table 7**

**Standard Composition**

Component	Manufacturer	Product Number	Amount (Wt. Percent)
Polypropylene	Exxon	Escorene 4772	55.63
Mica	Franklin Industrial Minerals, Inc.	L-140	30.0
Calcium Carbonate	Huber	Q-325	10.0
Coupling Agent	Aristech	Unite NP-620	2.5
Titanium Dioxide	Tioxide	TR-23	1.87

The above components were extruded on a 90 mm Berstorff Co-Rotating Twin Screw Extruder with underwater pelletizing under the following conditions:

- 200 rpm screw speed
- with the following set temperature profile:

Zone 1 - 510°F

Zone 2 -485°F

Zone 3- 400°F

Zone 4-380°F

Zone 5 -380°F

Zone 6-380°F

Head Flange -425°F

Screen Changer-425°F

Die-440°F

Throughput appx. 900 LB/HR

to produce the standard pellets. By the foregoing definition, these standard pellets have a relative aroma intensity index (RAII) of 1.0.

- 5        The preferred instrument to perform the aroma intensity measurements is an Aroma Scan® model A32 (*AromaScan, Hollis, New Hampshire, USA*). This instrument employs a dynamic head space type of measurement, in which nitrogen gas flows through a sample vial and carries aroma volatiles to the sensors. All pellet samples are analyzed in triplicate with the final results averaged to
- 10       minimize measurement noise. In the illustrations which follow, The "Acquisition Parameters" method of the instrument is set with a sampling interval of 1 and a detection threshold of 0.2. The "Multisampler-SP" method of the instrument sets the platen temperature (100°C for the examples herein). Two other temperatures (115° C and 125° C) are automatically set. The Multisampler-SP method is also
- 15       used to set the parameters in Table 8 to measure aroma intensity.

**Table 8**  
**AromaScan® Settings**

Sample Equilibration Time:	5 minutes
Vial Size:	22 ml
Mix Time:	0
Mix Power:	1
Relative Humidity:	10%
Sampling Time:	4 minutes
Wash Time:	5 minutes
Data Collection Time (minutes):	19
Time Between Injections (minutes):	20

5        In the recognition window, start and end are set at 1. In addition to the foregoing, the "Vial Pressurization Control" is set at 20 kPa, the "Vial Needle Flow" is set at 50 ml/min nitrogen; "Transfer Line Flow" across the sensors, between, before and after samples is set at 150 ml/min. All gas flows are for dry nitrogen.

10        A response of each of the 32 sensors of the AromaScan® machine is integrated over a time interval of 55 – 150 seconds. The initial 55 seconds is allowed to let humidity/moisture exit the system to a great extent before integration is started. The 150 second integration end time was chosen to allow the sensor signals to return to baseline, at which time all significant signal has been  
15        integrated. The various signals seen after 150 seconds are insignificant in terms of the odor measurement, as can be seen from Figure 5. Figure 5 is a plot of sensor

response vs. time for each of the 32 sensors of the Aroma Scan device, where individual responses are shown as various lines on the diagram.

Using the foregoing procedure, 2.0 grams of compounded polymer pellets  
5 are weighed and placed in the 22 ml, crimp top, septum capped vials and analyzed automatically by the instrument. There is shown in Figure 6 the results for various extruded polypropylene/mica pellets. The data points shown on Figure 6 are actually the response integrals for a particular sensor.

10 The abscissa on Figure 6 indicates each of the 32 elements; while the ordinate is the time-integrated response of the corresponding element in arbitrary units. There is shown as curve A the (integrated) sensor responses for the standard sample prepared as above. As noted before, this sample has a relative aroma intensity index of 1.0 by definition. There is also shown a sample prepared  
15 in accordance with the standard sample procedure except that polypropylene was substituted for calcium carbonate at curve B as in the "high odor" compositions of the Kansas State Trials discussed above in connection with Examples 12 - 17. As can be seen, this composition has a relative aroma intensity index of about 1.6; or in other words, its response integrals are on average 1.6 times those of the  
20 standard sample. There is also shown on Figure 6 a third curve (C) representative of more preferred compositions prepared in accordance with the present invention. Curve C represents a composition prepared in accordance with Examples 28 through 30 below (Table 11) wherein the relative aroma intensity index is less than about 0.7 which means its response integrals are on average less than 0.7  
25 times those of the standard sample.

Through the use of an automated instrument, the aroma intensity of the melt-compounded pelletized composition can be reduced to a single value. While the foregoing sets forth a particular and preferred method of determining the  
30 relative aroma intensity index, it may also be possible to employ other instruments consistent with this protocol since such instruments are readily available. If such

alternative instrument is employed the standard composition detailed above should be used to ensure that calibration is proper. As noted, the standard composition has a RAI of 1.0 while a composition prepared substituting polypropylene for the calcium carbonate of the standard composition has a RAI of about 1.6 or above and a composition prepared in accordance with Examples 28 through 30 should have a RAI of 0.7 or less. By using these multiple reference points, the relative aroma intensity index is always readily determined by one of skill in the art.

10 **Examples 18 - 26**

A series of resin compositions and sheet products were prepared in accordance with the discussion above and characterized by C8/C7 ketone ratio and odor panel testing. Variables included calcium carbonate addition, process atmosphere (air or nitrogen) and process melt temperature. Results appear in Table 9 for examples 18 through 26.

Table 9  
CaCO<sub>3</sub> Effect of Process Conditions and Compositions on Odor of PP/Mica Composites

Example	Type (Banbury or Extruded Sheet)	Process Atmosphere (Air/N <sub>2</sub> )	CaCO <sub>3</sub> (Yes/No)	Process Melt Temperature	C <sub>8</sub> /C <sub>7</sub> Ketone Ratio	Odor Panel Data	
						Sustained (Total Intensity)	"Scorched" Odor Profile Component Intensity
18	Brabender Banbury Compounded	Air	Yes	370°F	0.055	2.0	0
19	Brabender Banbury Compounded	Air	Yes	460°F	0.6	4.0	5.0
20	Sheet	N <sub>2</sub>	Yes	460°F	0.3		
21	Brabender Banbury Compounded	Air	Yes	460°F	0.6	4.0	5.0
22	Sheet	Air	Yes	370°F	0.15	2.0	0
23	Sheet	Air	No	370°F	1.3	6.0	4.5
24	Sheet	Air	Yes	400°F	—	5.0	2.5
25	Sheet	Air	No	460°F	0.9	8.0	3.5
26	Sheet	Air	Yes	460°F	0.7	2.0	0

See discussion above for C<sub>8</sub>/C<sub>7</sub> ketone ratio, odor; Kansas State University Odor Panel Profile. Extruded Sheet was prepared using a single screw extruder with pre-compounded resin made by a twin screw process.

The resins of Examples 18, 19, and 21 were prepared on a Brabender device (C.W. Brabender, model EPL2V5502) with a Banbury mix head (model R.E.E.6, 230v, 11a) with a mixing time of 5-10 minutes

- 5 The sheet samples, Examples 20 and 22 through 26, were prepared from precompounded resin pellets extruded under the conditions shown in Table 10.

**Table 10**  
**Sheet Extrusion Conditions for PP/Mica Pilot Extruder**

CONDITIONS	ACTUAL	SET POINT
Barrel Zone 1 (°F)	354-378	360-375
Barrel Zone 2 (°F)	366-410	370-410
Barrel Zone 3 (°F)	371-460	370-460
Adapter temp (°F)	359-460	370-460
Feed Block Temp (°F)	370-468	370-460
Die Zones 1-3 temps (°F)	368-462	370-460
Extruder RPM	110	110
Drive Amperes	15-23	-
Melt Pressure (psi)	1050-1850	-
Die Pressure (psi)	745-910	-
Line Speed (FPM)	8.25-9.74	-
Chill roll temp. (°F)	130	-

10

The odor of PP/mica composites (pellets or sheet) is affected by temperature, atmosphere, and by the addition of a basic filler such as  $\text{CaCO}_3$ . The C8/C7 ketone ratio is consistent with the odor panel data and shows that offensive odor components decrease with:

- 15
- Using lower processing temperatures
  - Using a base such as  $\text{CaCO}_3$  as a buffering agent
  - Processing under inert atmosphere such as  $\text{N}_2$ .



•  
**Examples 27 - 30**

Particularly preferred, low odor compositions are prepared by way of a sequential process in a Banbury mixer at relatively low temperatures. A typical Banbury apparatus is shown schematically in Figure 7. An apparatus 110 includes generally a feed hopper 112 provided with a feed ram 114 coupled to a weight cylinder 116 which may be varied depending on the force required for a particular process. Feed hopper 112 has a lower portion 118 which communicates with a mixing chamber 120 provided with a pair of rotors 122, 124. The material is supplied to hopper 112 through a charging door indicated at 126, and/or fed through a feed port located at 128. Chamber 120 is further provided with a discharge door 130 which is positioned above a conveyor indicated at 132. Such apparatus is well known for compounding thermoplastic compositions.

A conventional non-sequential process is operated as follows: (a) discharge door 130 is closed; (b) ram 114 is drawn up; (c) the ingredients are added; (d) the ram is lowered and the rotors activated; (e) mixing is complete when a combination of temperature and work has been achieved (power draw on mixer motor falls off); (f) at which point the discharge door is opened and the batch is gravimetrically supplied to a conveyor; and finally (g) the batch is conveyed to a single screw extruder and pelletized. The apparatus melts the polymer through shear generated by the rotors and walls against the components being mixed. One may rely on shear (that is, mechanical work) to soften the thermoplastic components or apply some auxiliary heat directly either in the feed hopper or the chamber through the use of heating coils, infrared devices, steam jacketing and the like, or, alternatively, preheating the polymer externally prior to feeding.

It has been found that melt compositions prepared in a sequential Banbury process exhibit superior stiffness as measured by flexural modulus properties and

low odor. In a sequential process in accordance with the invention, two feed steps are used in order to minimize the time heated or molten polypropylene is in contact with the mica as will be explained in connection with Figures 7 and 8.

5        In a first, melt mix step, door 130 is closed and ram 114 is drawn up. Polypropylene, polyethylene, titanium dioxide, other pigments and the like are added. Ram 114 is lowered and the rotors 122, 124 are rotated to shear the material. A typical power curve (at constant rotor speed) for amperage supplied to the mixing motors for the inventive sequential process is shown in Figure 8, a plot  
10      of amperage versus time in hours:minutes:seconds.

      When the pair of rotating rotors are first started in the melt mix step, the current draw is indicated at point P1 on Figure 8 where it can be seen power applied to the polymer is quite high. The current draw reaches a maximum at  
15      about P2 where the polymer begins to soften rapidly. At P3 after a minute or two the current draw is at a minimum while the components are being mixed when the polymer is in a softened state. Mica and calcium carbonate may then be added simultaneously in a mica addition step as will be detailed below.

20        After the polymer is softened, ram 114 is again drawn up and the mica and calcium carbonate may be added at the time corresponding to P4 on the diagram. The material may be added through a door 126 or feed port 128. The current draw at constant rotor speed again increases as shown at P5 and eventually begins to decay as shown at P6 and P7. More preferred is to add the mica and calcium  
25      carbonate mixture at about the time corresponding to P2 prior to complete softening of the resin. Alternatively, polypropylene may be externally preheated to about 240° F or so (along with the mixing chamber to the same temperature) and all of the ingredients are simultaneously added for maximizing process throughput. Preferred drop batch temperature at the end of Banbury melt  
30      compounding, that is, maximum melt processing temperature for this step is up to about 425 degrees Fahrenheit. At the time corresponding to P7, the door may be

opened and the batch of material (a batch size is about 200 pounds) conveyed to an extruder to be pelletized.

Table 11

5. Comparison of Compounding Processes

COMPOUNDING PROCESS	Compound Flexural Modulus (Tangent), PSI	9" Plate Rigidity (g/0.5")	Relative Aroma Intensity Index (Compound)
Twin Screw Example 27	718,000	417	1.0
Banbury (non-sequential) Example 28	591,000	378	0.59
Banbury (sequential, 1 min. pre-heat) Example 29	708,000	416	0.65
Banbury (Sequential, 2 min. premelt) Example 30	635,000	352	0.62

Table 11 shows compound flexural modulus (as measured by ASTM method D 790-95a), corresponding plate rigidity, and aroma intensity index on four indicated compounding processes designated as examples 27 - 30. In the case of twin-screw (Example 27), high modulus is obtained but with higher odor with relatively low throughput, in the range of 900 lb/hr, which is less than half the output of Banbury compounding processes (utilizing a Stewart-Bolling Banbury Mixer with batch sized in the range of 150-200 lb) listed herein. In the case of non-sequential Banbury process, low modulus is obtained with corresponding low plate rigidity with lower odor and high throughput. In the last two cases corresponding to sequential Banbury processes designated as "1 min. pre-heat" and "2 min. pre-melt", the short 1 minute preheat case (Example 29) is preferred because it gives high compound modulus and high plate rigidity (comparable to twin screw case) with benefits of both low odor and high throughput, in excess of 2000 lb/hr.

The twin screw formulation in the above table contains PP/30% mica/10% CaCO<sub>3</sub> with 2.5 % coupling agent (maleic anhydride modified PP grade Aristech Unite NP -620) and no polyethylene. The formulation corresponding to all three

listed Banbury processes in above table contain PP/30% mica/10% CaCO<sub>3</sub>/0.5% TiO<sub>2</sub>/4%LLDPE with no coupling agent where such ingredients have the following sources and grades: Mica = Franklin Minerals L-140, CaCO<sub>3</sub> = Huber Q325, PP = Exxon Escorene PP4772, LLDPE = Novapol Novachemical G1-2024A.

The Banbury "non-sequential" case (Example 28) in Table 11 corresponds to adding all ingredients together with a total compounding time of about 4.5 minutes followed by conversion of the batch (having temperature of 430°F) to pellets using a continuous 10" single screw extruder equipped with one 30 mesh and one 20 mesh screen, and an underwater pelletizing die assembly, with a pelletizing temperature in the range of 455-470°F.

The Banbury "sequential 2 min premelt" case (Example 30) in Table 11 corresponds to a 2 minute period for melting the PP/LLDPE mixture (in the presence of CaCO<sub>3</sub> and TiO<sub>2</sub>) to a maximum temperature of about 350°F, followed by adding mica and thereafter mixing for a period of about 105 sec to achieve a batch temperature of about 430°F, followed by conversion to pellets with a pelletizing temperature of about 460°F. The Banbury "sequential, 1 min pre-heat" case (Example 29) in Table 11 corresponds to about a 1 minute period for presoftening the PP/PE mixture (in the presence of TiO<sub>2</sub>, or alternatively adding the TiO<sub>2</sub> with the mica and calcium carbonate) to a maximum temperature of about 260°F, followed by adding the mica/CaCO<sub>3</sub> mixture and thereafter mixing to achieve a batch temperature of about 425°F, followed by conversion to pellets with a pelletizing temperature of about 425°F. In this preferred mode, it has been found that polymer preheating aids in preserving compound stiffness (required for rigid articles of manufacture) and intimate contact of mica with odor suppressing agent (CaCO<sub>3</sub>) aids the production of low odor material.

Pellets from the above mentioned Banbury compounding processes were subsequently extruded at 370°F as cast sheets in the range of 17-18 mil. Sheet

line conditions also included a screw RPM value of 100, a chill roll temperature of about 130°F, drive amperage value of about 22, melt pressure of about 2000 psi, die pressure of about 970 psi, and a line speed of about 7 ft/min. Plates were subsequently vacuum thermoformed using a female mold and trimmed and tested for rigidity.

### **Examples 31 - 41**

Extruded mica filled polypropylene sheets prepared as described in Examples 1 through 8 were characterized with respect to surface gloss and roughness. Table 12 shows 75 degree gloss and Parker Roughness (airflow method) data for an extruded mica filled polypropylene sheet versus same properties for the food contact (air) side of vacuum formed 10.25 inch plates produced according to condition (B) of Figure 2 using the same sheet formulation. The unique thermally induced micronodular surface is characterized by significant decrease in gloss and significant increase in roughness as shown in the two photomicrographs in Figures 9A and 9B, which results in a stoneware or pottery like appearance with aesthetic appeal. (The Parker Roughness method is described above). The upper photomicrograph of Figure 9A is of a thermoformed plate surface, while the lower photomicrograph of Figure 9B is of sheet.

The photomicrographs of Figures 9A and 9B were obtained from a 10 x 15 mm piece cut out of a plate bottom. The sheet sample was mounted with surface of interest up on a specimen stub, and coated with gold/palladium. The stub was placed in a JEOL 840A Scanning Electron Microscope (SEM). Photomicrographs of the samples were taken at 75x magnification, 30 degree tilt, 39 mm working distance at 3kv.

**Table 12**

**GLOSS AND ROUGHNESS PROPERTIES OF THE FOOD CONTACT**

**SIDE OF**

**POLYPROPYLENE/MICA/TIO<sub>2</sub>**

**PLATE SURFACE VERSUS NEAT EXTRUDED SHEET**

EXAMPLE	GLOSS (75 DEGREES) *	PARKER ROUGHNESS (MICRONS)
31 (Plate)	22.4	13.41
32 (Plate)	30.6	14.05
33 (Plate)	24.8	14.89
34 (Plate)	24.3	14.24
35 (Plate)	24.5	12.48
PLATE AVERAGE	25.3 ± 3.1	13.8 ± 0.9
36 (Sheet)	45.7	5.92
37 (Sheet)	47.2	7.43
38 (Sheet)	-	5.89
39 (Sheet)	-	6.35
40 (Sheet)	-	5.84
41 (Sheet)	-	8.15
SHEET AVERAGE	46.5	6.6 ± 0.97

\* = Average of Machine and Cross Machine Directions

As shown in Table 12, the food contact side is rougher as evidenced by increased roughness and decreased gloss relative to the neat extruded sheet. The rough appearance is desirable for purpose of creating the micronodular surface giving the container and plate a stoneware or pottery-like look.

**Examples 42 - 43**

Mica filled polypropylene sheets were successfully vacuum thermoformed into 12 oz. oval microwave containers, whereby the base was produced using mode (B) of Figure 2 and the lid was produced using mode (A) of Figure 2. In

contrast, attempts to form unfilled polypropylene sheet into the same container were not successful.

**Examples 44 – 46**

5

Sheet rolls (17.5 wide), at three calipers were extruded as described in Examples 1 through 8 in connection with Figure 1. Table 13 summarizes the PP/40% mica material and process conditions. Table 14 summarizes the PP/40% mica sheet properties.

**Table 13**  
**PP/Mica Extrusion Process Conditions Summary**

Plate Size (in.)	Barrel Zone 1 Temp.(F) Actual/Set	Barrel Zone 2 Temp.(F) Actual/Set	Barrel Zone 3 Temp.(F) Actual/Set	Adaptor Temp.(F) Actual/Set	Feed Block Temp. Actual/Set	Line Speed (fpm)	Die Zone 1 Temp.(F) Actual/Set	Die Zone 2 Temp.(F) Actual/Set	Die Zone 3 Temp.(F) Actual/Set	Screw RPM Actual/Set	Drive Amperes	Melt Pressure (psi)	Die Pressure (psi)	Chill Roll Temp. (F) Actual/Set
11	395/395	452/425	475/475	470/470	470/470	9.27	470/470	469/470	470/470	125	18.3	1387	694	130/130
10	376/375	410/410	431/430	430/430	430/430	8.32	430/430	430/430	430/430	130	19.3	2012	737	130/130
9	375/376	410/410	434/430	430/430	430/430	8.07	430/430	430/430	430/430	132	24.2	2112	686	130/130

**Table 14**  
**PP/Mica Sheet Property Summary**

Plate Size (in.)	Overall Caliper -Avg. (mil)	Overall Basis Weight - Avg. (lb./3000 ft.^2)
11	18.46±0.36	308.07±13.72
10	17.20±0.10	288.80±9.89
9	16.94±0.10	268.11±7.50



**Example 47 - 49**

Plates from sheet specifications set forth in Examples 31 - 41 were produced using 1-up water cooled female molds ( with pressure box/vacuum assembly), followed by matched metal punch trimming. Mold temperature was 70°F, while sheet temperatures for the 9, 10, and 11 inch plate runs were respectively 300°F, 310°F, and 295°F. The 9 and 10 inch plates were produced at 20 cycles/minute while the bulk of the 11 inch plates were made at 25 cycles/minute.

Oven temperature control on the commercial machine was good due to the combination of top quartz heaters and bottom calrod heaters with proper zoning. In general, higher temperatures produce more micronodularity at the expense of more pronounced sheet sag and wrinkling while low temperatures tend to reduce sag at the expense of diminished stoneware or pottery-like appearance.

Best results (i.e., micronodular matte eating surface without "webbing" or wrinkling) were obtained by increasing the top oven temperature by 3-5°F and decreasing the bottom by a corresponding amount. This ability to selectively control oven temperature in effect facilitated determination of the preferred process temperature window of PP/mica sheets.

**Examples 50 - 54**

Sheets and plates were prepared as illustrated in Examples 1 through 8 and Figures 1 and 2. Table 15 shows sheet extrusion and forming conditions. Figures 10 and 11 respectively, show gloss and plate rigidity versus mica level (at constant mica/TiO<sub>2</sub> ratio).

**Table 15****Extrusion/Forming Conditions**

Barrel Zone 1	375°F
Barrel Zone 2	410°F
Barrel Zone 3	430°F
Adaptor	430°F
Feedblock	430°F
Die Zones 1/2/3	430°F
RPM	130
Chill Roll	130°F
Target Sheet Caliper	18.3 mil
Sheet Width	18.0 inches
Comet Former Top Heater	20%
Comet Former Bottom Heater	35%
Comet Former Time	50-60 seconds
Plate Diameter	11 inch

**Examples 55 - 62**

5

Commercial sheet extrusion runs of several mica filled polypropylene formulations were conducted. These sheets suitably have a basis weight of about 200 to 950, per 3000 square foot ream, preferably about 200 to 400 per 3000 square foot ream. These mica filled polypropylene sheets had a mica content in the range of 25 to 35 weight percent.

10

The extrusion of coupled mica and polypropylene blends was conducted on a 6" commercial extruder line. The extruder was an Egan 24/1 L/D with a general purpose screw. The die was an Extrusion Die Inc. 52" coat hanger type.

15 The stack conditioning rolls were top polished chrome, middle matte (40 RA

surface), and bottom polished chrome. The matte chill roll assisted with the formation of the micronodular surface during thermoforming of the sheet with beneficially improving breadth of forming temperature window in contrast with non-matted smooth sheets. The differences between surfaces of the various sheets and plates made therefrom may be better appreciated by reference to Figures 12 and 13 hereof. Figure 12A is a scanning electron photomicrograph of surface A of Table 16, while Figure 12B is a scanning electron photomicrograph of surface B of Table 16. Figure 13A is a scanning electron photomicrograph of surface G of Table 16 and Figure 13B is a scanning electron photomicrograph of surface H of Table 16.

The roughness of various surfaces is compared in Table 16 below.

**Table 16**  
**Roughness and Gloss Properties of**  
**PP/30% Mica Extruded Sheets and Thermoformed Plates**

Surface	Sheet Thermoforming Temperature (°F)	Parker Roughness (microns)	Gloss (75%)
A	-	$8.56 \pm 0.39$	$4.99 \pm 0.11$
B	-	$15.82 \pm 0.74$	$8.05 \pm 0.30$
C	305	$13.14 \pm 0.74$	$14.3 \pm 1.0$
D	300	$11.74 \pm 0.86$	$11.6 \pm 1.0$
E	292	$12.10 \pm 0.82$	$11.7 \pm 1.0$
F	265	$10.63 \pm 0.68$	$8.20 \pm 0.6$
G	-	6.17	82.10
H	-	5.14	80.75

(A) Matte extruded sheet having top matte side.

(B) Extruded sheet (A) – bottom side opposite to matte side

(C,D,E,F) Plate – eating side corresponding to top matte side of (A)

(G) Non-matte extruded sheet – top side (no matte roll)

(H) Non-matte extruded sheet – bottom side (no matte roll)

For a non-matte extruded sheet, usually plate gloss and plate roughness are inversely related (e.g., high gloss corresponds to low roughness and vice versa as demonstrated in prior art data generally obtained). In that case, achieving desirable micronodular texture is within a temperature range (about 295°F to

5 305°F) where above this range the forming process is sag limited while below this range the plate exhibits poor micronodular character as manifested by high gloss and low roughness.

The use of a matte roll in the chill roll stack portion of the extrusion  
10 process effectively broadens the commercially attractive thermoforming process temperature range (about 265°F to 305°F). Specifically, plates having acceptable surface micronodularity can be formed at lower temperatures, whereby the decrease in plate roughness is compensated by an unexpected decrease in plate gloss using sheet surface (A). This beneficial increase in plate forming  
15 temperature window from about 10°F to about 40°F is brought about by imparting a matte surface finish to the extruded sheet.

The extruded sheet used in the suitable forming and thermoforming process, or the preferred thermoforming process as shown in Figure 2 has a  
20 thickness of about 0.010 to 0.080 inches, suitably 0.010 to 0.030 inches, and preferably 0.015 to 0.25 inches. Suitable mica filler loading level in the extruded sheet is in the range of 25-30 weight percent, whereby mica flake aspect ratio is in the range of 30-300, more preferably 80-120, with particle size range of about 50-500 microns.

25

By matte finishing one side of the sheet using matte roll, the commercial thermoforming was suitably conducted at a broader temperature window of about

265°F to 305°F while without matte finishing, the thermoforming using the same commercial equipment was conducted at a temperature of about 295°F to 305°F.

5 The runs on commercial equipment using PP/30% mica and PP/25% mica formulations showed that the thermoforming-temperature window range has been expanded from about 10°F (previous trial) to as high as about 35°F. This is primarily due to the fact that we beneficially used a matte roll in the chill roll stack during the extrusion process. This gave a smooth matte finish for the air side of the sheet (i.e., plate eating surface) while the rougher bottom side was in  
10 contact with the sandblasted mold side during the forming process. Use of matte sheet, in turn, enabled forming at lower temperatures (which is good for sag avoidance) without much loss in micronodularity. Specifically, the forming window was in the range of 265°F to about 300°F to 305°F where best balance of process stability and product appearance/texture was seen at about 280°F to  
15 290°F.

### Preferred Articles

The sheet of the present invention is suitably formed into plates or bowls having a circular configuration. These articles of manufacture may also be square  
20 or rectangular in shape having angular corners, such as found in a tray. Further, additional shapes such as triangular, multi-sided, polyhexal, etc., are contemplated including compartmented trays and plates as well as oval platters. In each contemplated embodiment, all corners are rounded or curved with a preferred plurality of embodiments of the present invention being depicted in Figures 14  
25 through 33. The various embodiments shown in Figures 14 through 33, while illustrative of the present invention, are not intended to limit the invention and those of skill in the art may make changes without changing the essential characteristics of the invention. These containers may also have other features such as ridges, emboss, and deboss patterns suitable for enhancing the properties

of the containers of this invention. These container's bottom sections may have a convex crown to improve stability and reduce rocking during use.

Throughout the following description, each of the dimensions are  
5 referenced with respect to a given diameter D which, in accordance with the present invention as illustrated in Figures 14 through 17 is approximately 8.75 inches. However, the particular diameter of the container is not a critical limitation and is only set forth herein by way of example. It is the relationship between the various portions of the rim configuration which are essential.

10

The planar inner region in accordance with the illustrated embodiment of a plate in Figures 14 through 17 has a radius X1 which is equal to approximately  $0.3 D - 0.4 D$  and preferably  $0.348 D$ . This plate is described generally in United States Patent No. 5,326,020 the disclosure of which is incorporated herein by  
15 reference. Adjoining an outer periphery of the planar inner region 150 is a sidewall portion 152 including annular region 154 having a radius of curvature equal to approximately  $0.05 D - 0.06 D$  and preferably  $0.0572 D$  with the center point thereof being positioned a distance Y1 from the planar inner region 150. Included angle 156 of the annular region 154 is from about  $40^\circ$  to about  $70^\circ$  and  
20 preferably about  $60^\circ - 65^\circ$  or approximately  $62^\circ$ . Adjoining the periphery of the annular region 154 is the first frusto-conical region 158 which slopes upwardly at an angle A1 with respect to the vertical from about  $20^\circ$  to about  $35^\circ$  and preferably about  $25^\circ - 30^\circ$  or approximately  $27.5^\circ$ . Additionally, the frusto-conical region 158 is adjacent to the arcuate annular region 160 which includes a radius of  
25 curvature in the range of  $0.015 D$  to  $0.03 D$  and preferably approximately  $0.024 D$  with the center point thereof being positioned a distance Y2 from the planar inner region 150. The included angle 162 of the arcuate annular region 160 may range from about  $61^\circ$  to about  $82^\circ$  and is preferably  $66^\circ$  to  $77^\circ$  or about  $73^\circ$ . The second portion 164 of the arcuate annular region 160, that is the distal portion of the  
30 arcuate annular region 160, is positioned such that a line tangent to the curvature

of the arcuate annular region 160 at the second portion 164 slopes downwardly and outwardly at an angle of approximately  $0^{\circ}$  to  $12^{\circ}$ .

The combination of the annular region 154 and arcuate annular region 160  
5 should combine to position the second portion 164 of the arcuate annular region  
160 in the manner set forth herein above. That is, the included angle 156 of the  
annular region 154 when combined with the included angle 162 of the arcuate  
annular region 160 with the first frusto-conical region 158 spanning therebetween,  
positions the second portion 164 of the arcuate annular region 160 in a manner  
10 such that a second frusto-conical region 166, which extends substantially  
tangentially from the distal end of the second portion 164 of the arcuate annular  
region 160 extends outwardly and downwardly at an angle of about  $0^{\circ}$  to  $12^{\circ}$ .

The second frusto-conical region 166 is of a length in a range from about  $0.03 D$   
to about  $0.05 D$  and is preferably  $0.04 D$ . Because the second frusto-conical  
15 region 166 extends substantially tangentially from the second portion 164 of the  
arcuate annular region 160, the second frusto-conical region 166 extends  
outwardly and downwardly at an angle  $A3$  in the range from approximately  $0^{\circ}$  to  
 $12^{\circ}$  with respect to a horizontal plane formed by the planar inner region 150.

20 Adjoining an outer periphery of the second frusto-conical region 166 is the  
lip 168 which is in the form of yet another frusto-conical region which extends  
outwardly and downwardly from the second frusto-conical region 166. The lip  
168 is of a length of at least  $0.005 D$  and is preferably approximately  $0.010 D$ .  
Further, the lip (168) extends at an angle  $A2$  of no more than  $45^{\circ}$  from vertical,  
25 preferably approximately  $15^{\circ}$  to  $30^{\circ}$  with respect to the vertical plane.

At the transition between the second frusto-conical region 166 and the lip  
168 is a transition region 170. The transition region 170 includes a radius of  
curvature  $R3$  which is in the range of about  $0.008 D$  and  $0.01 D$  and is preferably  
30 approximately  $0.0092 D$  with the center point thereof being positioned a distance

Y3 from the planar inner region 150. Additionally, the transition region 170 has an included angle A4 of approximately 48° to 70°.

The plates disclosed in Figures 18 through 20 generally have the dimensions of the plates disclosed in U.S. Patent 5,088,640 which is incorporated herein by reference in its entirety. These containers may have other features such as ridges, emboss, and deboss patterns suitable for enhancing the properties of the containers of this invention. There is shown in Figures 18 through 20 a plate having a planar center including an outer peripheral surface. The planar center forms a bottom for the plate. An outwardly projecting sidewall includes a first rim portion joined to the outer peripheral surface of the planar center and a second rim portion joined to the first rim portion. The first and second rim portions form a sidewall of the plate. A third rim portion is joined to the second rim portion of the outwardly projecting sidewall and a fourth rim portion is provided for forming an outer edge of the container. The first rim portion is joined to the peripheral surface of the planar center at an angle having a second predetermined radius. The third rim portion is joined to the second rim portion at an angle having a third predetermined radius. The fourth rim portion is joined to the third rim portion at an angle having a fourth predetermined radius. The four radii as well as the four included angles are selected for enhancing rigidity of the plate as compared to a container made from the same material by other means as is further described below.

Illustrated in FIGS. 18-20, there is a plate 180 which includes a planar center 182 which, in turn, includes an outer peripheral surface 184. This center region 182 may have a slight convex crown to improve plate stability during use. The planar center 182 forms a bottom for the plate 180. An outwardly projecting sidewall 186 includes a first rim portion 188 which is joined to the outer peripheral surface 184 of the planar center 182. A second rim portion 190 is joined to the first rim portion 188. The first rim portion 188 and the second rim portion 190 form the outwardly projecting sidewall 186 which forms the sidewall



of the plate 180. A rim 192 includes a third rim portion 194 which is joined to the second rim portion 190 of the outwardly projecting sidewall 186. A fourth rim portion 196 is joined to the third rim portion 194. The fourth rim portion 196 forms the outer edge of the plate 180.

5

FIG. 20 illustrates a partial cross-sectional view of a plate, diameter D, according to the present invention. The plate 180 defines a center line 204. A base or bottom-forming portion 200 extends from the center line 204 to an outer peripheral surface 202.

10

From the center line 204 a predetermined distance X12 extends toward the outer peripheral surface forming portion 202. A distance Y12 extends a predetermined distance from the base or bottom-forming portion 200 upwardly therefrom. A radius R12 extends from the intersection point of the distance X12 and Y12 to form a first rim portion 206 of the outwardly projecting sidewall 205. The first rim portion 206 is defined by an arc A12 which extends from the vertical line defined at the outer peripheral surface 202 to a fixed point 210. The arc A12 may be approximately 60°.

15

A distance X22 extends from the center line 204 to a predetermined point. A distance Y22 extends from the base or bottom-forming portion 200 of the plate 180 downwardly a predetermined distance. A radius R22 extends from the intersection of the lines X22 and Y22 to form a second rim portion 208 of the sidewall 205. The radius R2 extends from the first fixed point 210 to the second fixed point 212 through an arc A22. The arc A22 may be approximately 4°.

20

A distance X32 extends from the center line 204 to a predetermined distance. A distance Y32 extends from the base or bottom-forming section 200 of the plate 180 to project upwardly a predetermined distance. A radius R32 extends from the intersection of the lines X32 and Y32 to form the third rim portion 214 of the rim 216. The radius R32 extends from the second fixed point 212 to a third

25

fixed point 218. An arc A32 is formed between the second fixed point 212 and the third fixed point 218 to extend a predetermined distance. The arc A32 may be approximately 55°.

- 5           A distance X42 extends a predetermined distance from the center line 204. Similarly, a distance Y42 extends from the base or bottom-forming section 200 of the plate 180 to project outwardly. A radius R42 extends from the intersection of the lines X42 and Y42 to form a fourth rim portion 217 of the rim 216. An arc A42 is formed between the third fixed point 218 and a fourth fixed point 220 at diameter D from the center line. The arc A42 may be approximately 60°. A section 220 forms the outer edge of the plate.
- 10

- The container made according to the present invention may have any particular size as desired by the user so long as the relative profile dimensions are maintained. More specifically, ovals, rectangles with rounded corners and other shapes may be made having this profile. In various embodiments of the present invention the container may be a 9-inch or 11-inch plate with profile coordinates as illustrated in FIGS 18 through 20 having the dimensions, angles, or relative dimensions enumerated in Tables 17 through 19.
- 15

**Table 17**  
**Dimensions and Angles For 9" Plate**

<b><u>DIMENSION and ANGLES</u></b>	<b><u>VALUE (inches or degrees)</u></b>
R12	0.537
X12	3.156
Y12	0.537
R22	2.057
X22	5.402
Y22	0.760
R32	0.564
X32	4.167
Y32	0.079
R42	0.385
X42	4.167
Y42	0.258
A12	60.00°
A22	4.19°
A32	55.81°
A42	60.00°
D	9.00
BOTTOM CONVEX CROWN	0.06

**TABLE 18**  
**Dimensions and Angles For 11' PLATE**

<b><u>DIMENSION/ANGLES</u></b>	<b><u>VALUE (inches or degrees)</u></b>
R12	0.656
X12	3.857
Y12	0.656
R22	2.514
X22	6.602
Y22	0.929
R32	0.689
X32	5.093
Y32	0.097
R42	0.470
X42	5.093
Y42	0.315
A12	60.00°
A22	4.19°
A32	55.81°
A42	60.00°
D	11.00
BOTTOM CONVEX CROWN	0.06

**TABLE 19**  
**Dimensions For 9 and 11 INCH PLATE**

DIMENSION RATIO OR ANGLE	VALUES (Dimensionless or degrees)		
	PREFERRED	MINIMUM	MAXIMUM
R12/D	0.060	0.045	0.075
X12/D	0.351	0.280	0.420
Y12/D	0.060	0.045	0.075
R22/D	0.228	0.180	0.275
X22/D	0.600	0.480	0.720
Y22/D	0.084	0.065	0.100
R32/D	0.063	0.050	0.075
X32/D	0.463	0.370	0.555
Y32/D	0.009	0.007	0.011
R42/D	0.043	0.034	0.052
X42/D	0.463	0.370	0.555
Y42/D	0.029	0.023	0.035
A12	60.00°	55.00°	75.00°
A22	4.19°	1.00°	10.00°
A32	55.81°	45.00°	75.00°
A42	60.00°	45.00°	75.00°

- 5 Salient features of the plate illustrated in Figures 18 through 20 generally include a substantially planar center portion (which may be crowned as noted above and illustrated throughout the various figures) with four adjacent rim portions extending outwardly therefrom, each rim portion defining a radius of curvature as set forth above and further noted below. The first rim portion
- 10 extends outwardly from the planar center portion and is convex upwardly as shown. There is defined by the plate a first arc A12 with a first radius of curvature R12 wherein the arc has a length S1. A second rim portion is joined to the first rim portion and is downwardly convex, subtending a second arc A22, with a radius of curvature R22 and a length S2. A third, downwardly convex, rim

portion is joined to the second rim portion and subtends an arc A32. There is defined a third radius of curvature R32 and a third arc length S3. A tangent to the third arc at the upper portion thereof is substantially parallel to the planer center portion as shown in Figure 20. A fourth rim portion is joined to the third rim  
5 portion, which is also downwardly convex. The fourth rim portion subtends a fourth arc A42 with a length S4, with a radius of curvature R42.

The length of the second arc, S2 is generally less the length of the fourth arc S4, which, in turn, is less than the length S1 of the first arc A12. The radius of  
10 curvature R42 of the fourth arc is less than the radius of curvature R32 of the third rim portion, which in turn, is less than radius of curvature R22 of the second rim portion. The angle of the first arc, A12 is generally greater than about 55 degrees, while, the angle of the third arc, A32 is generally greater than about 45 degrees as is set forth in the foregoing tables. The angle of the fourth arc A42 is generally  
15 less than about 75 degrees and more preferably is about 60 degrees.

Typically, the length S1 of arc A12 is equivalent to the length S3 of arc A32 and R12 of the first rim portion is equivalent in length to the radius of curvature R32 of the third rim portion.  
20

Generally speaking, the height of the center of curvature of the first arc (that is the origin of ray R12) above the central planar portion is substantially less than, perhaps twenty five percent or so less than, the distance that the center of curvature of the second rim portion (the origin of ray R22) is below the central  
25 planar portion. In other words, the length Y12 is about 0.75 times or less the length Y22.

So also, the horizontal displacement of the center of curvature of the second rim portion from the center of curvature of the first rim portion is at least  
30 about twice the length of the first radius of curvature R12. The height of the center of curvature of the third rim portion above the central planar portion is

generally less than the height of the center of curvature of the fourth rim portion above the plane of the central planar portion. The horizontal displacement of the center of curvature of the second rim portion is generally outwardly disposed from the center of curvature of the third and fourth rim portions.

5

A final noteworthy feature of the plate of Figures 18 through 20 is that the height of the center of curvature of the third rim portion above the planar central portion is less than about 0.75 times the radius of curvature R42 of the fourth rim portion; while the height of the center of curvature of the fourth rim portion above the plane of the central portion is at least about 0.4 times the first radius of curvature R12.

Yet other embodiments of this invention include trays which have either the DIXIE® Superstrong profile as illustrated in Figures 21 through 24 and/or described in U.S. Patent 5,326,020 assigned to the assignee of the present invention and incorporated herein by reference into this application. These trays may have other features such as ridges, emboss, and deboss patterns suitable for enhancing the properties of the trays of this invention. Throughout the following description of Figures 21 through 24, each of the dimensions are referenced to either the length D1 or the width D2, which are approximately 10.90 and 8.00 inches respectively. D1 is larger than or equal to D2. However, the particular length and width of these containers is not a critical limitation and is only set forth herein by way of example. It is the relationship between the various portions of the rim configurations which are essential. The planar inner region 101 in accordance with the illustrated embodiment in Figures 21A through 24, has a length 1X which is equal to approximately 0.3 D1 to 0.4 D1 and 0.3 D2 to 0.4 D2 and preferably 0.354 D1 and preferably 0.342 D2. Adjoining an outer periphery of the planar inner region 230 is a sidewall portion 232 including annular region 234 having a radius of curvature equal to approximately 0.02 D1 to 0.03 D1 and 0.025 D2 to 0.035 D2 and preferably 0.023 D1 and 0.031 D2 with the center point thereof being positioned a distance Y1 from the planar inner region 230. Included

angle 236 of the annular region 234 is from about  $40^\circ$  to about  $80^\circ$  and preferably about  $65^\circ$  to  $75^\circ$  or approximately  $69^\circ$ . Adjoining the periphery of the annular region 234 is the first frusto-conical region 238 which slopes upwardly at an angle A1 with respect to the vertical from about  $10^\circ$  to about  $50^\circ$  and preferably about  $15^\circ$  to  $25^\circ$  or approximately  $21^\circ$ . Additionally, the frusto-conical region 238 is of a length greater than about  $0.05 D1$  and  $0.055 D2$ , preferably from about  $0.1 D1$  to  $0.2 D1$  and  $0.15 D2$  to  $0.25 D2$  and more preferably approximately  $0.15 D1$  and  $0.19 D2$ . Further, adjoining the first frusto-conical region 238 is the arcuate annular region 240 which includes a radius of curvature in the range of  $0.005 D1$  to  $0.007 D1$  and  $0.007 D2$  to  $0.009 D2$  and preferably approximately  $0.006 D1$  and  $0.008 D2$  with the center point thereof being positioned a distance Y2 from the planar inner region 230. The included angle 242 of the arcuate annular region 240 may range from about  $40^\circ$  to about  $92^\circ$  and is preferably  $65^\circ$  to  $87^\circ$ . The second portion 244 of the arcuate annular region 240, that is the distal portion of the arcuate annular region 240 is positioned such that a line tangent to the curvature of the arcuate annular region 240 at the second portion 244 slopes downwardly and outwardly at an angle of approximately  $0^\circ$  to  $12^\circ$ .

The combination of the annular region 234 and arcuate annular region 240 should combine to position the second portion 244 of the arcuate annular region 240 in the manner set forth herein above. That is, the included angle 246 of the annular region 234 when combined with the included angle 242 of the arcuate annular region 240 with the first frusto-conical region 248 spanning therebetween, positions the second portion 244 of the arcuate annular region 240 in a manner such that the second frusto-conical region 250, which extends substantially tangentially from the distal end of the second portion 244 of the arcuate annular region 240 extends outwardly and downwardly at an angle of about  $0^\circ$  to  $12^\circ$ . The second frusto-conical region 250 is of a length in a range from about  $0.045 D1$  to about  $0.055 D1$  and  $0.030 D2$  to about  $0.040 D2$  and is preferably  $0.052 D1$  and  $0.034 D2$ . Because the second frusto-conical region 250



extends substantially tangentially from the second portion 244 of the arcuate annular region 240, the second frusto-conical 250 extends outwardly and downwardly at an angle A3 in the range from approximately 0° to 12° with respect to a horizontal plane formed by the planar inner region 230.

5

Adjoining an outer periphery of the second frusto-conical region 238 is the lip 252 which is in the form of yet another frusto-conical region which extends outwardly and downwardly from the second frusto-conical region 250. The lip 252 is of a length of at least 0.006 D1 and 0.009 D2 and is preferably approximately 0.010 D1 and 0.013 D2. Further, the lip 252 extends at an angle A2 of no more than 45° from vertical, preferably approximately 10 to 30° with respect to the vertical plane and more preferably approximately 20°.

10

At the transition between the second frusto-conical region 250 and the lip 252 is a transition region 254. The transition region 254 includes a radius of curvature R3 which is in the range of about 0.005 D1 to 0.007 D1 and 0.007 D2 to 0.009 D2 and is preferably approximately 0.006 D1 and 0.008 D2 with the center point thereof being positioned a distance Y3 from the planar inner region 230.

15

Additionally, the transition region 254 has an included angle A4 of approximately 48° to 80°.

20

There is shown in Figures 25 through 28 still yet another embodiment of the inventive articles. Throughout the following description of Figures 25 through 28, each of the dimensions are referenced with respect to a given diameter D which, in accordance with the present invention as illustrated in Figures 25 through 28, is approximately 7.5 inches. However, the particular diameter of the containers is not a critical limitation and is only set forth herein by way of example. It is the relationship between the various portions of the rim configuration which are essential. The planar inner region 260 in accordance with the illustrated embodiment in Figures 25 through 28, has a radius X1 which is equal to approximately 0.2 D to 0.3 D and preferably 0.25 D. Adjoining an outer

25

30

periphery of the planar inner region 260 is a sidewall portion 262 including annular region 264 having a radius of curvature equal to approximately 0.05 D to 0.15 D and preferably 0.11 D with the center point thereof being positioned a distance Y1 from the planar inner region 260. Included angle 266 of the annular region 264 is from about 45° to about 75° and preferably about 60° to 70° or approximately 65°. Adjoining the periphery of the annular region 264 is the first frusto-conical region 268 which slopes upwardly at an angle A1 with respect to the vertical from about 15° to about 45° and preferably about 20° to 30° or approximately 25°. Additionally, the frusto-conical region 268 is of a length greater than about 0.1 D preferably from about 0.17 D to about 0.19 D and more preferably approximately 0.18 D. Further, adjoining the first frusto-conical is the arcuate annular region 270 which includes a radius of curvature in the range of 0.015 D to 0.030 D and preferably approximately 0.023 D with the center point thereof being positioned a distance Y2 from the planar inner region 260. The included angle 272 of the arcuate annular region 270 may range from about 45° to about 87° and is preferably 60° to 77°. The second portion 274 of the arcuate annular region 270, that is the distal portion of the arcuate annular region 270 is positioned such that a line tangent to the curvature of the arcuate annular region 270 at the second portion 274 slopes downwardly and outwardly at an angle of approximately 0° to 12°.

The combination of the annular region 264 and arcuate annular region 270 should combine to position the second portion 274 of the arcuate annular region 260 in the manner set forth herein above. That is, the included angle 266 of the annular region 264 when combined with the included angle 272 of the arcuate annular region 270 with the first frusto-conical region 264 spanning therebetween, positions the second portion 274 of the arcuate annular region 270 in a manner such that the second frusto-conical region 276, which extends substantially tangentially from the distal end of the second portion 274 of the arcuate annular region 270 extends outwardly and downwardly at an angle of about 0° to 12°.

The second frusto-conical region 276 is of a length in a range from about 0.02 D to about 0.04 D and is preferably 0.03 D. Because the second frusto-conical region 276 extends substantially tangentially from the second portion 274 of the arcuate annular region 270, the second frusto-conical region 276 extends  
5 outwardly and downwardly at an angle A3 in the range from approximately 0° to 12° with respect to a horizontal plane formed by the planar inner region 260.

Adjoining an outer periphery of the second frusto-conical region 268 is the lip 278 which is in the form of yet another frusto-conical region which extends  
10 outwardly and downwardly from the second frusto-conical region 276. The lip 278 is of a length of at least 0.01 D and is preferably approximately 0.017 D. Further, the lip 278 extends at an angle A2 of no more than 45° from vertical, preferably approximately 10° to 30° with respect to the vertical plane and more preferably approximately 25°.

15

At the transition between the second frusto-conical region 276 and the lip 278 is a transition region 280. The transition region 280 includes a radius of curvature R3 which is in the range of about 0.007 D and 0.012 D and is preferably approximately 0.009 D with the center point thereof being positioned a distance  
20 Y3 from the planar inner region 260. Additionally, the transition region 280 has an included angle A4 of approximately 48° to 80°.

There is shown in Figure 29 yet another embodiment of a food contact article in accordance with the present invention. The containers of this invention  
25 may be formed as take-out containers, and a representative embodiment, a suitable take-out container, will now be described in general with respect to Figure 29 wherein the lid and base may be formed as described in U.S. Patent 5,377,860 which is incorporated herein by reference. While the container illustrated in Figure 29 is oblong in configuration, the container may be round, oval,  
30 substantially rectangular or square as dictated by the contents which are to be placed within the container. The container 290 is formed of a base or bottom

portion 292 and a lid 294. The lid 294 includes radially extending opening tabs 296 which cooperate with the radially extending opening tabs 298 of the base 292 in order to allow the consumer to readily open the sealed container. The base 292 of the container 290 includes a substantially planar bottom 300 and a substantially vertically extending peripheral sidewall 302. Integrally connected to the upstanding sidewall 292 is a sealing brim 304 which is received within a cooperating sealing brim 306 of the lid 294.

The lid 294 includes a substantially planar top portion 308 and a rim 310 extending about a periphery of the top portion 308. The rim 310 is provided in order to enhance the strength of an extended volume portion 312 of the lid 294. The rim 310 also serves to locate the base 292 on the lid when the lid is used as a stand.

The extended volume portion 312 is formed by extension wall 314 positioned about the perimeter of the rim 310 and extending downwardly therefrom. The extension wall 314 is integrally formed with a horizontal lid reinforcing ring 316 which is substantially parallel to the top portion 308 of the lid 294. The outer perimeter of the lid reinforcing ring 316 is further integrally formed with the sealing brim 306. Also, extending radially outward from the sealing brim 306 is a second horizontal lid reinforcing ring 318 which extends substantially parallel to the top portion 308 as well.

Similarly, the base 292 includes a horizontal lid reinforcing ring 320 which extends from the periphery of the sealing brim 304 for aiding in and maintaining the structural integrity of the sealing brim 304 as well as the container 290 as a whole. In addition to the reinforcing ring 320, a step 322 may be provided about an upper portion of the peripheral sidewall 302 for preventing nested units from becoming jammed together due to excessive interpenetration when stacked and nested. Also, formed in an upper portion of the sidewall 302 are undercuts 324 which cooperate with detents 326, only one of which is illustrated in Figure 29 at

the integral connection between a brim 306 and lid reinforcing ring 316. The detents, when engaged in the undercuts 324, provide an audible indication that the container is in fact sealed. Additionally, undercuts 328 may be provided in an outer periphery of the brim 304 for receiving detents 330 formed in an outer portion of the brim 306 for again providing an audible indication that the container is sealed. While the container illustrated in Figure 29 shows detents and undercuts formed in both the inner and outer portions of the brims 324 and 306, respectively, it may be desired to provide respective detents and undercuts on only one side of the brim or to provide no undercuts and detents on either side of the brim.

In a yet still further embodiment of this invention another bowl is illustrated in Figures 30 through 33. Throughout the following description of the bowl of Figures 30 through 33, each of the dimensions are referenced with respect to a given diameter D which, in accordance with the present invention as illustrated is approximately 7.3 inches. However, the particular diameter of the containers is not a critical limitation and is only set forth herein by way of example. It is the relationship between the various portions of the rim configuration which are essential. The crowned inner region 340 in accordance with the illustrated embodiment in Figures 30 through 33, has a crown height Y5 which is approximately 0.004 D to 0.012 D or preferably 0.008 D, and encompassing a radius X1 which is equal to approximately 0.2 D to 0.3 D and preferably 0.25 D. Adjoining an outer periphery of the crowned inner region 340 is a sidewall portion 342 including first annular region 344 having a radius of curvature equal of approximately 0.05 D to 0.15 D and preferably 0.11 D with the center point thereof being positioned at distance Y1 from the tangency point between the crowned inner region 340 and the first annular region 344. Included angle 346 of the first annular region 344 is from about 45° to about 85° and is preferably 65° to 80° or approximately 72°. Adjoining the periphery of the first annular region 344 in the sidewall portion 342 is a second annular region 348 having a radius of curvature equal of approximately 0.8 D to 1.2 D and preferably

0.96 D with the centerpoint thereof being positioned a distance Y2 from the tangency point between the crowned inner region 340 and the first annular region 344. The included angle of arc A2 indicated generally at 350 of the second annular region 348 is from about 2° to 12° and is preferably 5° to 9° or approximately 7°. Adjoining the periphery of the second annular region 348 in the sidewall portion 342 is a third annular region 352 having a radius of curvature equal to approximately 0.1 D to 0.2 D and preferably 0.15 D with the centerpoint thereof being positioned a distance Y3 from the tangency point between the crowned inner region 340 and the first annular region 344. Included angle 354 of the third annular region 352 is from about 20° to 50° and is preferably 25° to 40° or approximately 33°. Adjoining the sidewall portion 342 is a flange portion 356 including a fourth annular region consisting of regions 358 and 360 which have the same radius of curvature. Adjoining the third annular region 352 is a fourth annular region beginning with annular region 358 which extends to the uppermost bowl height and continuing with annular region 360 to bowl diameter D. Annular regions 358 and 360 are equivalent to one annular region, flange portion 356 since both have the same radius of curvature of approximately 0.02 D to 0.05 D and preferably 0.03 D with the centerpoint thereof being positioned a distance Y4 from the tangency point between the crowned inner region 340 and the first annular region 344. Included angle 362 of the fourth annular region 356 is from about 45° to 85° and preferably 65° to 80° or approximately 73°.

#### **Physical Properties, Heat Resistance and Food Contact Suitability**

Figure 34 shows rigidity versus current plate material cost comparisons for mica filled polypropylene plates versus competitor plastic disposable plates. "J" refers to mica filled polypropylene plate of this invention and "S" refers to polystyrene based plates such as those currently manufactured by Solo Cup Company. Average plate calipers are indicated for each plate type and size. The left side of the diagram shows data for 8.75 inch plates whereby the J plate rigidity is about three times higher than S at significantly reduced caliper and cost. The

right side of the diagram shows data for 10.25 inch plates whereby J plated rigidity is more than seven times higher S at the same caliper. The open circle point corresponds to an estimated rigidity for the 10.25 inch J plate that is scaled down in caliper so that plate material costs are equivalent to S.

5

The scaled J caliper X is calculated as  $X = (19 \text{ mil})(2.9 \text{ cents}/3.8 \text{ cents})$ . The theoretical rigidity R1 at equivalent cost for the downscaled caliper is calculated as:

$$(R1/R2) = (14.5 \text{ mil}/19 \text{ mil}) \exp N$$

10

where R2 is the experimental rigidity at 19 mil and  $N = 1.816$  is the caliper exponent value for the Dixie-Superstrong 10.25 inch plate design which is obtained from the general equation for rigidity:

$$R = (KE) T \exp N$$

15 where E is Young's modulus, K is a shape constant, and T is caliper. The data set forth in Figure 34 demonstrate that the rigidity of the J plate of this invention is significantly higher at equivalent or lower material cost than commercial polystyrene polymer based plates.

20 In Figure 35, the heat resistance performance for mica filled polypropylene 10.25 inch plates (J), having an average caliper of 19 ml (J) is compared with (S) polystyrene based plates (S) of the same size and caliper. A measure of heat resistance is dynamic flexural storage modulus  $E'$ , as measured with the Rheometrics Solids analyzer at 10 rad/sec. Higher  $E'$  values indicate increased  
25 stiffness and improved dimensional stability. Dynamic mechanical spectroscopy is a common technique used for evaluation of viscoelastic properties of polymeric materials with respect to temperature and input frequency (deformation time scale). Dynamic mechanical properties of flat rectangular specimens of S plate material and PP/mica sheet of this invention were subjected to flexural  
30 deformation at 10 rad/sec, using the Rheometrics Solids Analyzer RSAII instrument, manufactured by Rheometric Scientific, and equipped with a dual

cantilever bending fixture. Temperature scans were conducted at 0.05% strain using 2°C temperature steps with a 0.5 minute soak time at each temperature. From the time lag between input strain delivered by the driver motor and the stress output measured by the transducer, values of material complex modulus  $E^*$  are obtained. The parameter  $E^*$  is formally expressed as  $E^* = E' + iE''$ , where  $E'$  is the storage modulus (purely elastic term) and  $E''$  is the loss modulus (purely viscous term). The storage modulus  $E'$  is defined as the stress in phase with the strain divided by the strain, which gives a measure of the energy stored and recovered per cycle. The loss modulus  $E''$  is defined as the stress 90 degrees out of phase with the strain divided by the strain, which gives a measure of the energy dissipated per cycle. The ratio of loss modulus to storage modulus is commonly known as the damping (tan delta) where delta is the phase angle between stress and strain. The dynamic storage flexural modulus  $E'$  is the operative measure of heat resistance performance, where higher values mean higher performance. At ambient conditions (77°F),  $E'$  for mica filled polypropylene plates of this invention is appreciably higher than for S. At 250°F, which corresponds to aggressive temperatures which are commonly encountered in the microwave heating or cooking of greasy foods, the heat resistance of J plates of this invention is significantly superior to the plates manufactured by S, as further demonstrated below in connection with microwave cooking trials.



Table 20

**MICROWAVE COOKING TEST RESULTS FOR PLATES J AND S**

<b>PLATE TYPE</b>		
<b>FOOD TYPE</b>	<b>J</b>	<b>S</b>
Donut	Pass	Sugar glazing sticks
Broccoli/cheese	Pass	Significantly deforms
Pepperoni pizza	Pass	Moderate deformation, Staining
Barbecue pork	Slight stain	Significant stain/warpage
Pancake/syrup	Pass	Significant warpage
Beans & pork	Pass	Significant warpage
Butter	Slight warpage	Significant warpage
Bacon	Moderate warpage Localized melting, no leak	Significant warpage Rubbery plate flows and Sticks to glass tray

**Microwaveability**

Fort James Corporation (J) plate specimens of this invention and plates manufactured by Solo Cup Company (S) were tested in the microwave (Samsung model MW 8690) with a variety of foods. The highest power setting (10) was

used in all cases and cooking/heating times and procedures corresponded to food manufacturer instructions on the packages. Most tested foods were of the frozen microwaveable type and were placed in a semi-thawed state directly on plates prior to cooking. When appropriate, a loose covering of wax paper was employed during the cooking process. After cooking, the plates were gently washed with warm water and inspected. The following are the detailed test results which are also summarized in above Table 20.

#### TEST #1 RESULTS - Sugar Glazed Donut

I A large, oval shaped sugar glazed plain donut was microwaved on the plate of this invention for 60 seconds. The sugar glazing melted, bubbled, and flowed on the plate. The boiling sugar and grease mixture caused the bottom of the plate to feel very warm but the plate exhibited no warping, no staining, no softening, and no soak-through. The plate was cool enough to be safely handled. The residue of the donut was easily washed off and the appearance of the used plate was excellent.

S The bottom of the plate got hot and slightly deformed with no soak-through, however, sugar stuck to the plate.

#### TEST #2 RESULTS - Broccoli With Cheese Sauce

I Green Giant 10 oz. Broccoli with cheese sauce was removed from the flexible pouch and heated for five minutes in the microwave on the plate with loose covering of wax paper. The cheese melted and bubbled on the plate without sticking. The plate bottom was warm, but no soak-through and no loss of dimensional stability was observed. After washing, no staining was observed and the appearance of the used plate was excellent.

S The plate bottom got hot and significantly deformed with no soak-through.

#### TEST #3 RESULTS - Pepperoni pizza

I Tombstone 7 oz. Pepperoni pizza was cooked on an uncovered plate for 4 minutes. The cheese melted and started bubbling about halfway

through the test. The molten cheese mingled with the hot liquid fat extruded from the pepperoni and dripped on the sides of the crust onto the plate. No sticking, no soak-through, no staining, and no loss in plate dimensional stability was observed and the appearance of the used plate was excellent.

- 5           S       The plate bottom got hot and moderately deformed with no soak-through. The greasy reddish stain from oil in pepperoni could not be completely washed off.

#### TEST #4 RESULTS - Microwave Kid Meal:

10                   Pork Rib Patties, Barbecue Sauce, Fries, Honey Corn Bread

- I       A quick meal preparation simulation test was conducted using a Swanson 7.2 oz. microwave kids' meal with ingredients consisting of partially cooked boneless pork rib patties, barbecue sauce, fries, and honey corn bread. The food was transferred from the compartmented tray onto the plate. Sauce was
- 15       spooned on top of the pork meat and was allowed to drip on the sides of the patties and onto the plate. The cornbread batter was spooned out and was placed on the plate next to the fries. The food was loosely covered with wax paper and cooked for 3.5 minutes. Examination after microwaving showed that the cornbread was fully cooked and there was no sticking or damage to the plate. The
- 20       fries and pork meat with sauce caused no soak-through and no loss in plate dimensional stability. Washing of plate revealed the presence of slight staining from barbecue sauce. Overall, the appearance of the used plate was very good.

- S       The plate bottom deformed mainly from pork meat with considerable staining from the barbecue sauce without soak-through.

25

#### TEST #5 RESULTS - Beans With Pork and Tomato Sauce

- I       Beans with pork and tomato sauce (8 oz. Can) were placed on the plate, covered with wax paper and heated for 2 minutes near boiling. The bottom of plate got hot, but the rim was cool to touch. The hot plate bottom exhibited no
- 30       bulging and also, when the hot food plate was handled by the rim there was no

perceived loss in dimensional stability. No soak-through, no warping and no staining was observed. The appearance of the plate was excellent.

S The plate bottom became very hot and severely deformed with no soak-through and when handled by the rim, the plate felt like it had low rigidity.

5

#### TEST #6 RESULTS - Pancakes With Syrup and Precooked Bacon

I In this test, Swanson microwave pancakes and bacon breakfast (4.5 oz. size) were used. The semi-thawed meal consisted of three pancakes and three partially, precooked bacon strips. The pancakes and bacon were removed from the tray in carton and placed on plate. Approximately 5 teaspoons of pancake syrup was spooned over the pancakes and the assembled meal was covered with wax paper and microwaved for 2 minutes. Although the bottom of the plate got hot, the overall plate performance was excellent, i.e. no warpage, no soak-through, no loss in dimensional stability, and no staining. Some hot grease was exuded by the bacon during crisping but there was no observed damage to the plate. The appearance of the used plate was excellent.

10

S The plate bottom became hot and significantly deformed (especially in areas where bacon was placed), but no soak-through was observed and when handled by the rim, the plate felt soft.

20

#### TEST #7 - Butter

I Butter (5-tsp. chunk) was placed on the plate and was loosely covered with wax paper and was microwaved for 3 minutes. The butter melted completely and covered the whole plate bottom. The butter began boiling toward the end of the test. The plate bottom got very hot and became slightly warped but no soak-through. The rim of the plate felt cool to touch enabling safe removal of the plate from the microwave oven. A small portion of the butter became charred but was easily washed off the plate. Overall plate performance was good.

25

S The plate bottom became very hot and was significantly warped but no soak-through was observed and the greasy film residue could not be washed off completely. Plate felt soft and rubbery when handled by the rim.

30

**TEST #8 RESULTS - Bacon**

J Three strips of raw, cured bacon were wrapped in three sheets of paper towel and cooked for 5 minutes. All of the bacon became crispy and about 20% of it was charred. The bottom of plate got very hot but most of the rim area was relatively cool to the touch. Grease exuded from bacon and soaked through the towel. The grease pooled on the plate bottom, side and on some rim areas. The grease which pooled in some rim regions caused localized melting of the plate but no holes were formed. The hot grease which pooled on plate bottom caused significant warpage but no soak-through. Overall plate performance for Test #8 was less satisfactory than Test #7.

S When the raw bacon was wrapped in paper toweling and cooked on the S plate, the bottom became very soft and stuck to the glass tray in the microwave. Under such hot grease conditions, the adhering polymer regions underwent localized melting and stretched when the plate was lifted off the glass tray. The plate was severely warped but no holes formed and no soak-through was noticed.

With the possible exception of raw bacon, the behavior of the J plate of this invention in the microwave oven is considered excellent with a variety of aqueous, greasy/fatty, sugary food combinations. No unusual or off odors were detected during and after cooking for each type of food directly on the plate. The foregoing data demonstrates the superior properties of the plates of this invention.

**Crack Resistance**

Low temperature crack resistance of rigid plates is of paramount importance when considering that product must survive during storage and shipping to point of sale. Normally, it is difficult to improve crack resistance or reduce brittleness of rigid polymeric materials without reducing the stiffness which is usually the case when introducing excessive amounts of softer extensible materials such as polyethylenes, rubber modified resins and the like. In order to

be successful in imparting crack resistance without significantly reducing stiffness, one must add relatively low amounts of polyethylene or rubber modified additives, generally in the range of several to about 5 wt%. However, this invention shows that addition of low levels of polyethylene alone is not sufficient  
5 to promote crack resistance whereby the desired result is produced by a synergistic binary combination of polyethylene and  $\text{TiO}_2$ . Such low odor products have high crack resistance which renders them useful in the commercial sense.

10 **Examples 63 - 70**

There is provided in a still further aspect of the invention toughened, crack resistant articles. It has been found that  
polypropylene/mica/polyethylene/titanium dioxide formulations without a coupling agent resist cracking. Generally, the articles have the components set  
15 forth in Table 21, in the amounts mentioned above in the summary of the invention herein. In Table 21, it is demonstrated that polyethylene/titanium dioxide exhibit synergy in resisting cracking.

Table 21

Low Temperature crack data for 9 inch plates made of  
PP/30% mica/10% CaCO<sub>3</sub> modified with various combinations  
of TiO<sub>2</sub>, polyethylene, or coupling agent

Example #	TiO <sub>2</sub> (wt%)	LLDPE (wt%)	HDPE (wt%)	Coupling Agent (wt%)*	Percent Cracked plates at 0 F**
63	---	4	---	---	100 (n=5)
64	---	---	---	2.5	100 (n=5)
65	1.9	---	---	---	100 (n=5)
66	---	4	---	2.5	100 (n=5)
67	1.9	0	0	2.5	100 (n=5)
68	0.5	4	---	2.5	60 (n=5)
69	0.5	4	0	0	0 (n=5)
70	0.5	0	4	0	0 (n=10)

- Coupling agent is maleic anhydride modified PP grade Aristech Unite NP-620;
  - other ingredients are: Mica = Franklin Minerals L 140, CaCO<sub>3</sub> = Huber Q325,
  - PP = Exxon Escorene PP4772, LLDPE = Novapol Novachemical G1-2024A
- \*\* percentage of plates which cracked at 0° F for specimen sets comprised of the indicates number n

Crack resistance of Examples 63 through 70 was evaluated in the laboratory according to method set forth below which was found useful as an investigative tool for optimizing the formulation with various combination of TiO<sub>2</sub>, polyethylene, or coupling agent. A laboratory procedure was devised and used to evaluate the crack resistance of plates. Specifically, following is a description of test instruments and associated fixtures used to subject plates to a repeatable rim crushing force. The model numbers of standard equipment used on this procedure are recited below and additional fixtures used in these tests were employed as follows:

Instron – Model #55R402 was used which was equipped with Instron Environmental Chamber Model #3111. The Instron environmental chamber – Model #3111 was modified to control low temperatures with liquid nitrogen. It

was equipped with a control solenoid mounted on the rear of the cabinet and an electronic control module mounted on the control panel assembly. The temperature within the chamber was controlled in relationship to the setpoint on the front panel temperature dial. A thermocouple within the chamber provides  
5 feed back to the device. A mercury thermometer was placed in the chamber and oriented so that temperature within the chamber was visible through an insulated glass door. It was monitored and adjusted to 0°C using the panel temperature dial.

10 A push rod was attached to the load cell of the instron and was passed through an opening in the top of the environmental chamber. A circular metal device measuring 100 mm in diameter and 10 mm in thick was attached to the end of the push rod inside the chamber. This circular metal device was used to contact the edge of a plastic plate during testing.

15 The plate support fixture was placed on a circular metal base support which measured 140mm in diameter by 14 mm thick. This metal base support was located just above the inside floor of the environmental chamber. It was attached to a support rod that passes through the floor of the environmental chamber and attached to the base of the instron. Centering stops were provided on  
20 the metal base support so that the plate support fixture could be repeatedly placed at the same location in the environmental cabinet.

The plate support fixture is constructed of 5-mm thick sheets of plexiglas. The main base of this fixture measures 100 x 125 mm. The 125-mm dimension  
25 represents the width of the front of the mixture. The edge of the 125 mm side of a second plexiglas panel measuring 160 x 125 mm was permanently attached to the plexiglas main base. This panel was attached at a 90° angle to the main base and 35 mm in from the front edge. An L shaped plexiglas component was attached to the main base behind and parallel to the permanent panel by thumbscrews. Two  
30 20-mm long slots were provided in the base of the L shaped component to allow attachment and provide movement for adjustment to hold the test plate. The short



leg or base of the L shaped component faces the rear of the fixture. A block measuring 40x25x15 mm thick was permanently attached at the upper most end at the center of the L shaped component. This block is located on the front side of the moveable component or just opposite the short leg of the L shaped component, while an adjustable plate stop was attached to one side of the moveable L shaped component.

The methodology for testing the crack resistance of plates was as follows. The test plate was secured in a vertical position on edge in the plate support fixture. The bottom of the test plate was placed against the permanently attached plexiglas panel of the plate support fixture. The thumbscrews were loosened on the moveable portion of the plate support fixture. The L shaped moveable component was moved toward the plate. The plate was held in a vertical position by the fixed plexiglas panel and the block which was attached to the wall of the L shaped moveable component.

The plate stop located on the L shaped moveable component was adjusted so that the center of the plate would align with the center of the plate support fixture. The plate support fixture along with the test plate secured in a vertical position was placed on the metal base support in the environmental chamber. The instron was adjusted so that the push rod crush assembly was located 0.5 inches above the plate edge.

Prior to the test, the environmental chamber was adjusted to 0°F. After placement of the plate support fixture along with the test plate secured in a vertical position in the environmental chamber, the chamber had to re-establish 0°F. This time period was about 30 seconds. After re-establishment of the test temperature, the plate was conditioned for an additional five minutes prior to the test.

The crosshead speed of the instron was set at 40 inches per minute. After the five minute conditioning time period, the instron was activated and the edge

crushing force applied. A set of five or a set of ten replicate plates was tested for each condition. The total number of plates tested and the total number plates showing rim crack failure for each condition tested are reported in Table 21. In addition, the percentage of plates which cracked was calculated as shown above.

5

The above formulations for crack resistance testing were compounded in the temperature range of 400 to about 425 F on commercial Banbury equipment using batch sizes in the range of 150-200 lb and nominal mixing times of 3 min followed by underwater pelletizing.

10

Pellets were subsequently extruded at 370 F as cast sheets in the range of 18 mil. Sheet line conditions also included a screw RPM value of 100, a chill roll temperature of 130 F. Plates were subsequently vacuum thermoformed using a female mold, trimmed, and thereafter tested for crack resistance.

15

Data on Examples 63 through 65 show that presence of TiO<sub>2</sub>, polyethylene, or coupling agent alone is not sufficient to promote crack resistance of plates comprised of PP/mica/CaCO<sub>3</sub>. In addition, data on Examples 66 and 67 show that binary combinations of polyethylene with coupling agent or TiO<sub>2</sub> with coupling agent are two cases which are also not sufficient for imparting crack resistance. Furthermore, the tertiary combination of TiO<sub>2</sub>, polyethylene, and coupling agent (Example 68) also does not impart sufficient crack resistance, as evidenced by the majority of samples which exhibit cracking. Rather, the useful additive packages of this invention (Examples 69 and 70) comprises the binary system of polyethylene (either LLDPE or HDPE) with at least 0.5 wt% TiO<sub>2</sub> whereby crack resistance is excellent as evidenced by no cracked samples.

20

25

#### **Examples 71-78**

30

Additional plates were fabricated in accordance with the foregoing procedures and compositions; crack testing results appear in Table 22 below

**Table 22**  
**Crack Data and Physical Properties for Various Compounded Formulations**  
**Base Formulation: PP/30% Mica / 10% CaCO<sub>3</sub>**

Example	Formulation			Melt Flow g/10 min. @230°C	Filler Content (Wt. %)	Flexural Modulus Tangent (psi)	9" Plate Rigidity (grams/0.5")	Product Weight (grams)	Crack Data @0°F (#Cracked Total)
	TiO <sub>2</sub> (wt.%)	PE (4 wt. %)	Coupling Agent*						
71	0	LLDP E	No	1.45	39.4	505,000	288	19.3	5/5
72	1.9	LLDP E	No	1.64	40.6	581,600	422	23.13	0/5
73	1.2	LLDP E	No	2.05	39.8	578,500	385	22.12	0/5
74	0.5	LLDP E	No	1.77	38.6	487,500	286	20.65	0/5
75	1.9	HDPE	No	1.5	40.6	637,500	436	22.70	1/5
76	1.9	0	Yes	1.9	39.0	717,585	417	21.25	5/5
77	1.9	LLDP E	Yes	1.6	39.6	494,000	391	21.6	5/5
78	1.9	0	Yes	1.2	40.3	593,000	353	20.8	5/5

\*When present, coupling agent concentration is 2.5

## CLAIMS

1. A microwaveable, disposable food contact article having food contact compatible olfactory properties formed from a melt-processed polyolefin/mica composition wherein said composition includes from about 40 to about 90 percent by weight of a polypropylene polymer and from about 10 to about 50 percent by weight mica and wherein said melt processed composition exhibits a relative aroma intensity index of less than about 1.6 .
2. The microwaveable article according to Claim 1, wherein said melt-processed composition further includes a basic organic or inorganic compound comprising the reaction product of an alkali metal or alkaline earth element with carbonates, phosphates, carboxylic acids as well as alkali metal and alkaline earth element oxides, hydroxides, or silicates and basic metal oxides, including mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures thereof.
3. The microwaveable article according to Claim 2, wherein the basic organic or inorganic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium citrate, potassium citrate, sodium citrate, calcium stearate, potassium stearate, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicon dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the above.
4. The microwaveable article according to Claim 3, wherein the basic inorganic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium

oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the basic inorganic compounds set forth above, wherein the  
5 amount of the basic inorganic compound is from about 2 to about 20 weight percent of said article.

5. The microwaveable article according to Claim 4, wherein said basic inorganic compound is calcium carbonate.

10 6. The microwaveable article according to Claim 5, wherein calcium carbonate is present in said article from about 5 to about 20 weight percent.

15 7. The microwaveable article according to Claim 3, wherein said basic organic compound is selected from the group consisting of sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, and mixtures of these wherein the amount of the basic organic compound is from about 0.5 to about 2.5 weight percent of said article.

20 8. The microwaveable article according to Claim 1, wherein said composition exhibits a relative aroma intensity index of less than about 1.0.

25 9. The microwaveable article according to Claim 8, wherein said composition exhibits a relative aroma intensity index of less than about 0.7.

10. The microwaveable article according to Claim 1, wherein said article is a bowl or a plate.

30 11. The microwaveable article according to Claim 1, wherein said article is produced by injection molding.

12. The microwaveable article according to Claim 1, wherein said article is thermoformed from a sheet made from melt-extruded polypropylene/mica pellets.
- 5 13. The article according to Claim 12, wherein said article is formed, thermoformed, vacuum thermoformed by application of pressure, thermoformed by application of vacuum, or thermoformed by a combination of vacuum and pressure, into the shape of a container; said container exhibiting a melting point of no less than about 250°F, said container being dimensionally stable and resistant to grease, sugar and water at temperatures up to at least 220°F and of sufficient toughness to be resistant to cutting by serrated polystyrene flatware.
- 10
14. The microwaveable article according to Claim 12, wherein said article has at least one micronodular food contact surface.
- 15
15. The microwaveable article according to Claim 14, wherein said micronodular surface is produced through vacuum thermoforming on the side opposite said micronodular food contact surface.
- 20
16. The microwaveable article according to Claim 14, wherein said micronodular food contact surface exhibits a surface gloss of less than about 35 at 75° as measured by TAPPI method T-480-OM 92.
- 25
17. The microwaveable article according to Claim 16, wherein said micronodular food contact surface exhibits a Parker Roughness Value of at least about 12 microns.
- 30
18. The microwaveable article according to Claim 1, wherein said polypropylene polymer is selected from the group consisting of: isotactic polypropylene, co-

polymers of propylene and ethylene wherein the ethylene moiety is less than about 10 percent of the units making up the polymer and mixtures thereof.

- 5 19. The microwaveable article according to Claim 18, wherein said polymer is isotactic polypropylene and has a melt-flow index from about 0.3 to about 4.
20. The microwaveable article according to Claim 19, wherein said polypropylene has a melt flow index of about 1.5.
- 10 21. The microwaveable article according to Claim 1, wherein said composition further includes a polyethylene component.
- 15 22. The microwaveable article according to Claim 21, wherein said polyethylene is selected from the group consisting of HDPE, LDPE, LLDPE, MDPE and mixtures thereof.
23. The microwaveable article according to Claim 21 wherein said polyethylene component comprises HDPE.
- 20 24. The microwaveable article according to Claim 21, wherein said polyethylene component comprises LLDPE.
- 25 25. The microwaveable article according to Claim 21, further including titanium dioxide.
26. The microwaveable article according to Claim 1, wherein said article exhibits a melting point of from about 250 to about 330°F.
- 30 27. The microwaveable article according to Claim 1, wherein mica is present in said melt-processed composition from about 20 to about 35 weight percent.

28. The microwaveable article according to Claim 27, wherein mica is present in said melt-processed composition at about 30 weight percent.
29. The microwaveable article according to Claim 1, wherein said article is substantially free from volatile C8 and C9 organic ketones.
30. The microwaveable article according to Claim 1, wherein said article is prepared from a melt compounded polyolefin/mica composition which is produced at a process melt temperature of less than about 425°F.
31. The microwaveable article according to Claim 30, wherein said article is produced from a melt compounded polyolefin/mica composition which is prepared at a temperature below about 400°F.
32. The microwaveable article according to Claim 30, wherein said article is thermoformed from an extruded sheet produced from a melt compounded polyolefin/mica composition which was prepared at a process melt temperature of less than about 425°F.
33. The microwaveable article according to Claim 1, wherein said melt processed polyolefin/mica composition is melt compounded in a nitrogen atmosphere.
34. The article of manufacture according to Claim 1, in the form of a plate having a substantially planar center portion;
- a first rim portion extending outwardly therefrom, said first rim portion being upwardly convex and subtending a first arc with a first radius of curvature;



a second rim portion joined to said first rim portion, and extending outwardly therefrom, said second rim portion being downwardly convex, subtending a second arc with a second radius of curvature;

5 a third rim portion joined to said second rim portion and extending outwardly therefrom, said third rim portion being downwardly convex, subtending a third arc with a third radius of curvature as well as a tangent thereto which is substantially parallel to the plane of said substantially planar center section; and,

10 a fourth rim portion joined to said third rim portion and extending outwardly therefrom, said fourth rim portion being downwardly convex subtending a fourth arc having a fourth radius of curvature, wherein the length of said second arc of said second rim portion is substantially less than the length of said fourth arc of said fourth rim portion which, in turn, is substantially less than the length of said first arc of said first rim portion  
15 and wherein said fourth radius of curvature of said fourth rim portion is less than said third radius of curvature of said third rim portion which, in turn, is less than said second radius of curvature of said second rim portion and wherein the angle of said first arc is greater than about 55 degrees and  
20 the angle of said third arc is greater than about 45 degrees.

35. The plate according to Claim 34, wherein the angle of said fourth arc is less than about 75 degrees.

25 36. The plate according to Claim 34, wherein the length of said first arc is substantially equivalent to the length of said third arc and said first radius of curvature of said first arc is substantially equivalent to said third radius of curvature of said third arc.

30 37. The plate according to Claim 34, wherein the height of the center of curvature of said first rim portion above the plane of said substantially planar portion is

substantially less than the distance by which the center of curvature of said second rim portion is below the plane of said substantially planar portion.

- 5 38. The plate according to Claim 34, wherein the horizontal displacement of the center of curvature of said second rim portion from the center of curvature of said first rim portion is at least about twice said first radius of curvature of said first rim portion.
- 10 39. The plate according to Claim 34, wherein said height of the center of curvature of said third rim portion above the plane of said substantially planar portion is less than the height of the center of curvature of said fourth rim portion above the plane of said substantially planar portion.
- 15 40. The plate according to Claim 34, wherein the horizontal displacement of the center of curvature of said second rim portion is located outwardly from the center of curvature of both said third and fourth rim portions.
- 20 41. The plate according to Claim 34, wherein the height of the center of curvature of said third rim portion above the plane of said substantially planar portion is less than about 0.75 times the radius of curvature of said fourth rim portion and the height of the center of curvature of said fourth rim portion above the plane of said substantially planar portion is at least about 0.4 times said first radius of curvature of said first rim portion.
- 25 42. A microwaveable, disposable food contact article having food contact compatible olfactory properties formed of a melt-processed polyolefin/mica composition wherein said composition includes from about 40 to about 90 percent by weight of a polypropylene polymer and from about 10 to about 50 percent by weight mica and a basic organic or inorganic compound
- 30 comprising the reaction product of an alkali metal or alkaline earth element with carbonates, phosphates, carboxylic acids as well as alkali metal and

alkaline earth element oxides, hydroxides or silicates and basic metal oxides, including mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures thereof.

- 5 43. The microwaveable article according to Claim 42, wherein the basic organic or inorganic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium citrate, potassium citrate, 10 calcium stearate, potassium stearate, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicon dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the above.
- 15 44. The microwaveable article according to Claim 43, wherein the basic inorganic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium 20 phosphate, mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the basic inorganic compounds set forth above, wherein the amount of the basic inorganic compound is from about 5 to about 20 weight percent of said article.
- 25 45. The microwaveable article according to Claim 44, wherein said basic inorganic compound is calcium carbonate.
- 30 46. The microwaveable article according to Claim 45, wherein calcium carbonate is present in said article from about 8 to about 12 weight percent.

47. The microwaveable article according to Claim 42, wherein said basic organic compound is selected from the group consisting of sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, and mixtures of these wherein the amount of the basic organic compound is from about 0.5 to about 2.5 weight percent of said article.
48. A low temperature compounding process for preparing polypropylene/mica melt compounded product which includes a basic odor-suppressing agent having olfactory properties suitable for food contact applications comprising the sequential steps of : (a) preheating a polypropylene polymer while maintaining the polymer below a maximum temperature of about 350°F; followed by (b) admixing mica to said pre-heated polymer in an amount from about 10 to about 50 percent by weight based on the combined weight of resin and mica; followed by (c) extruding said mixture.
49. The process according to Claim 48, wherein said maximum temperature of Step (a) is about 260°F.
50. The process according to Claim 48, wherein said polymer is melted through the application of shear.
51. The process according to Claim 48, wherein said polypropylene polymer is preheated prior to said admixing step externally to the vessel in which said step of admixing the mica takes place.
52. The process according to Claim 48, wherein the duration of Step (b) is a maximum of about 5 minutes.
53. The process according to Claim 48, wherein the duration of Step (b) is a maximum of about 3 minutes.

54. The process according to Claim 48, wherein said basic odor suppressing agent is added to the mixture simultaneously with said mica in step (b) of the process.

5 55. The process according to Claim 54, wherein said steps of preheating said polymer and admixing said mica and odor suppressing compound to said resin are carried out in a batch mode in a mixing chamber provided with a pair of rotating rotors.

10 56. The process according to Claim 48, wherein said odor suppressing compound is a basic organic or inorganic compound comprising the reaction product of an alkali metal or an alkaline earth element with carbonates, phosphates, carboxylic acids, as well as alkali metal and alkaline earth element oxides, hydroxides or silicates, basic metal oxides including mixtures of silicon  
15 dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the organic or inorganic compounds set forth above.

20 57. The process according to Claim 56, wherein the basic organic or inorganic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium citrate, potassium citrate, sodium stearate, calcium stearate, potassium stearate, sodium phosphate, potassium phosphate,  
25 magnesium phosphate, mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the organic or inorganic compounds set forth above.

30 58. The process according to Claim 57, wherein the basic inorganic compound is selected from a group consisting of calcium carbonate, sodium carbonate,

potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, mixtures of silicon dioxide with one or more of the following oxides:

5 magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the basic inorganic compounds set forth above and wherein the amount of the basic inorganic compound is from about 5 to about 20 weight percent of the composition.

- 10 59. A process for forming a microwaveable, disposable, rigid and strong, mica and basic inorganic or organic compound filled polyolefin container having food contact compatible olfactory properties, said polyolefin being selected from the group consisting of polypropylene and polypropylene polyethylene
- 15 copolymer or blend, and a mixture of these wherein the inorganic or organic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium
- 20 phosphate, sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, hydroxides of these elements, and mixtures of these organic compounds, mixtures of silicon dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures of one or more of the basic inorganic or organic compounds set forth herein, comprising the steps of:
- 25
- (a) forming an extrudable admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound;
- (b) extruding said extrudable admixture of the polyolefin resin, mica, and the basic inorganic compound or the basic organic
- 30 compound at elevated temperature;

- (c) passing the resulting extruded admixture of the polyolefin resin and mica and the basic inorganic compound or the basic organic compound through a multiple roll stack, at least one roll of said stack having a matte finish;
- 5 (d) thermoforming said extruded admixture of the polyolefin, resin, mica, and the basic inorganic compound or organic compound; and
- (e) recovering a container having a micronodular surface and exhibiting a melting point of no less than 250°F, said container being dimensionally stable and resistant to grease, sugar, and water at temperatures up to about 220°F and having sufficient toughness to be resistant to cutting by serrated flatware wherein the amount of the basic inorganic compound or basic organic compound added is sufficient to reduce carbonyl moiety
- 10 containing decomposition products to provide containers with suitable food contact compatible olfactory properties.
- 15

60. A process for forming a microwaveable, disposable, rigid and strong, mica and basic inorganic or organic compound filled polyolefin container having food contact compatible olfactory properties, said polyolefin being selected from the group consisting of polypropylene and polypropylene polyethylene copolymer or blend, and a mixture of these wherein the inorganic or organic compound is selected from the group consisting of calcium carbonate, sodium carbonate, potassium carbonate, barium carbonate, aluminum oxide, sodium silicate, sodium borosilicate, magnesium oxide, strontium oxide, barium oxide, zeolites, sodium phosphate, potassium phosphate, magnesium phosphate, sodium stearate, calcium stearate, potassium stearate, sodium citrate, potassium citrate, corresponding hydroxides of the foregoing elements and mixtures of these organic compounds, mixtures of silicon dioxide with
- 20 one or more of the following oxides: magnesium oxide, calcium oxide,
- 25
- 30

barium oxide, and mixtures of one or more of the basic inorganic or organic compounds set forth herein, comprising the steps of:

- 5
- (a) forming an extrudable admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound;
- (b) extruding said extrudable admixture of the polyolefin resin, mica and the basic inorganic compound or the basic organic compound at elevated temperature;
- 10
- (c) passing the resulting extruded admixture of the polyolefin resin and mica and the basic inorganic compound or the basic organic compound through a multiple roll stack, at least one roll of said stack having a matte finish;
- 15
- (d) passing said extruded admixture of the polyolefin resin, mica, and basic inorganic compound or the basic organic compound at least partially around said roll having a matte finish;
- (e) controlling the speed of said extrusion process, the size, temperature and configuration of said roll stack such that the surface of said extruded admixture of the polyolefin resin, mica, and the basic inorganic or organic compound not in
- 20
- contact with said matte roll has a coarse-grained structure;
- (f) thermoforming said extruded admixture of the polyolefin, resin, mica, and the basic inorganic compound or organic compound; and
- 25
- (g) recovering a container having a micronodular surface and a rough surface and exhibiting a melting point of no less than 250°F, said container being dimensionally stable and resistant to grease, sugar, and water at temperatures up to about 220°F and having sufficient toughness to be resistant to cutting by serrated flatware wherein the amount of the basic inorganic
- 30
- compound or basic organic compound added is sufficient to reduce carbonyl moiety containing decomposition products



associated with odor to provide containers with suitable food contact compatible olfactory properties.

- 5 61. The process of claim 60 wherein the coarse-grained structure of the surface of said extruded admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound not in contact with said matte roll is formed by transversing the extruded admixture of the polyolefin resin, mica, and the basic inorganic compound or basic organic compound through a curvilinear path and at least partially solidifying the surface of said extruded admixture of polyolefin resin, mica, and the basic inorganic compound or basic organic compound not contacting said matte roll while that surface is in tension relative to the surface contacting said matte roll.
- 10 62. The process of claim 60 wherein the container is a plate.
- 15 63. The process of claim 60 wherein the container is a cup.
64. The process of claim 60 wherein the container is a bowl.
- 20 65. The process of claim 60 wherein the container is a tray.
66. The process of claim 60 wherein the container is a lid.
- 25 67. The process of claim 60 wherein the container is a compartmented tray.
68. The process of claim 60 wherein the container is a bucket.
69. The process of claim 60 wherein the container is a soufflé dish.
- 30 70. A crack-resistant, thermoformed food contact article having a wall thickness from about 10 to about 80 mils consisting essentially of from about 40 to

about 90 percent by weight of a polypropylene polymer, from about 10 to about 50 percent by weight mica, from about 1 to about 15 percent by weight polyethylene, from about 0.1 to about 5 weight percent titanium dioxide and optionally including a basic organic or inorganic compound comprising the  
5 reaction product of an alkali metal or alkaline earth element with carbonates, phosphates, carboxylic acids as well as alkali metal and alkaline earth element oxides, hydroxides, or silicates and basic metal oxides, including mixtures of silicone dioxide with one or more of the following oxides: magnesium oxide, calcium oxide, barium oxide, and mixtures thereof.

10

71. The crack-resistant, thermoformed food contact article according to claim 70, wherein said basic organic or inorganic compound comprises calcium carbonate and said calcium carbonate is present in an amount of from about 5 to about 20 weight percent

15

72. The crack-resistant, thermoformed food contact article according to claim 70 wherein polyethylene is present from about 2.5 to about 15 percent by weight.

20

73. The crack-resistant, thermoformed food contact article according to claim 72, wherein polyethylene is present from about 4 to about 5 weight percent.

74. The crack-resistant, thermoformed food contact article according to claim 70, wherein titanium dioxide is present from about 0.1 to about 3 weight percent.

25


75. The crack-resistant, thermoformed food contact article according to claim 74, wherein titanium dioxide is present from about 0.25 to about 2 percent by weight.

30

76. The crack-resistant, thermoformed food contact article according to claim 70 wherein titanium dioxide is present in an amount of at least about 0.5 percent by weight.

77. The crack-resistant, thermoformed food contact article according to claim 70,  
wherein said article has a wall caliper of from about 10 to about 50 mils.
- 5 78. The crack-resistant, thermoformed food contact article according to claim 77,  
wherein said article has a wall caliper of from about 15 to about 25 mils.
79. The crack-resistant, thermoformed food contact article according to claim 70,  
wherein said mica is an untreated mica.
- 10 80. The crack-resistant, thermoformed food contact article according to claim 70,  
wherein said polypropylene polymer is isotactic polypropylene.
- 15 81. The crack-resistant, thermoformed food contact article according to claim 80,  
wherein said isotactic polypropylene has a melt index of from about 0.3 to  
about 4.
- 20 82. The crack-resistant, thermoformed food contact article according to claim 81,  
wherein said isotactic polypropylene has a melt flow index of about 1.5.
83. The crack-resistant, thermoformed food contact article according to claim 70,  
wherein said polyethylene is HDPE.
- 25 84. The crack-resistant, thermoformed article according to claim 70, wherein said  
polyethylene is LLDPE.

FIG. 1



2/29

FIG. 2





FIG. 3



SUBSTITUTE SHEET (RULE 26)

4/29

FIG. 4





FIG. 5




SUBSTITUTE SHEET (RULE 26)




6/29

FIG. 6




**FIG. 7**



**SUBSTITUTE SHEET (RULE 26)**

8/29

FIG. 8




9/29

*FIG. 9A*



*FIG. 9B*



SUBSTITUTE SHEET (RULE 26)

10/29

FIG. 10





FIG. 11



11/29

FIG. 12A





FIG. 12B



SUBSTITUTE SHEET (RULE 26)

12/29

FIG. 13A




FIG. 13B




FIG. 14A





FIG. 14B



SUBSTITUTE SHEET (RULE 26)



14/29

FIG. 15A




FIG. 15B




FIG. 15C




FIG. 16





FIG. 17



SUBSTITUTE SHEET (RULE 26)

16/29

FIG. 18




FIG. 19





FIG. 20



SUBSTITUTE SHEET (RULE 26)

18/29

FIG. 21A




FIG. 21B




FIG. 22A




FIG. 22B





FIG. 22C

FIG. 22C



SUBSTITUTE SHEET (RULE 26)

20/29

FIG. 23




FIG. 24




FIG. 25A





FIG. 25B



SUBSTITUTE SHEET (RULE 26)



22/29

FIG. 26A




FIG. 26B




FIG. 26C

FIG. 26C




FIG. 27





FIG. 28



SUBSTITUTE SHEET (RULE 26)

24/29

FIG. 29




FIG. 30A





FIG. 30B



SUBSTITUTE SHEET (RULE 26)

26/29

FIG. 31A




FIG. 31B




FIG. 31C




FIG. 32





FIG. 33



SUBSTITUTE SHEET (RULE 26)

28/29

FIG. 34





FIG. 35



SUBSTITUTE SHEET (RULE 26)



# INTERNATIONAL SEARCH REPORT

In tional Application No

PCT/US 99/05465

## A. CLASSIFICATION OF SUBJECT MATTER

IPC 6 B65D85/00 B65D81/00 C08L23/10 C08K3/34

According to International Patent Classification (IPC) or to both national classification and IPC

## B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 6 B65D C08L C08K

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

## C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	<p>DATABASE WPI Section Ch, Week 8815 Derwent Publications Ltd., London, GB; Class A32, AN 88-100548 XP002108103 &amp; JP 62 265332 A (MITSUI TOATSU CHEM INC) , 18 November 1987 see abstract</p>	1-84
A	<p>EP 0 407 198 A (SUMITOMO CHEMICAL CO) 9 January 1991 see page 3, line 27 - line 39 see page 6, line 18 - line 27</p> <p style="text-align: center;">--- -/-- ---</p>	1-84

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

### \* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search

2 July 1999

Date of mailing of the international search report

14/07/1999

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2  
NL - 2280 HV Rijswijk  
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,  
Fax: (+31-70) 340-3016

Authorized officer

Siemens, T

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	<p>DATABASE WPI                      Section Ch, Week 9043                      Derwent Publications Ltd., London, GB;                      Class A18, AN 90-326027                      XP002108104                      &amp; JP 02 235632 A (SHOWA DENKO KK)                      , 18 September 1990                      see abstract</p>	1-84
A	<p>-----                      US 5 377 860 A (LITTLEJOHN MARK ET AL)                      3 January 1995                      see figure 1                      see claim 1                      -----</p>	34-41

# INTERNATIONAL SEARCH REPORT

Information on patent family members

Int l tional Application No

PCT/US 99/05465

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
EP 0407198 A	09-01-1991	JP 2813891 B	22-10-1998
		JP 3041135 A	21-02-1991
		JP 2813892 B	22-10-1998
		JP 3041136 A	21-02-1991
		CA 2019884 A	07-01-1991
		DE 69013246 D	17-11-1994
		DE 69013246 T	24-05-1995
		US 5100930 A	31-03-1992
US 5377860 A	03-01-1995	CA 2127311 A	15-03-1995

**THIS PAGE BLANK (USPTO)**